



PROJECT
10010201

0000010

82011

VOLUME II of III

TECHNICAL MEMORANDUM NO. 1
INVESTIGATION RESULTS AND ANALYSIS REPORT

REMEDIAL INVESTIGATION/FEASIBILITY STUDY
H.O.D. LANDFILL
ANTIOCH, ILLINOIS

OCTOBER 1993

PREPARED FOR:
WASTE MANAGEMENT OF ILLINOIS, INC.
WESTCHESTER, ILLINOIS

• • •

PREPARED BY:
WARZYN INC.
ADDISON, ILLINOIS

TABLE OF CONTENTS

VOLUME I

1

INTRODUCTION.....	1-1
1.1 Purpose of Report.....	1-1
1.2 Background.....	1-1
1.2.1 Site Description.....	1-1
1.2.2 Location.....	1-2
1.3 Scope.....	1-3
1.4 Report Organization.....	1-3

2

REMEDIAL INVESTIGATION ACTIVITIES.....	2-1
2.1 Site Mapping and Surveying.....	2-1
2.2 Source Characterization.....	2-2
2.2.1 Landfill Cap Evaluation.....	2-2
2.2.2 Leachate Collection System Effectiveness.....	2-5
2.2.3 On-Site Surficial Soil/Sediment Sampling.....	2-5
2.2.4 Leachate Piezometer/Gas Well Installation.....	2-6
2.2.5 Perimeter Landfill Gas Probe Installation.....	2-7
2.2.6 Downhole Geophysical Logging.....	2-7
2.2.7 Leachate Sampling.....	2-8
2.2.8 Landfill Gas Sampling.....	2-8
2.2.9 Landfill Soil Borings.....	2-9
2.2.10 Evaluation of Off-Site Sources.....	2-9
2.3 Hydrogeologic Investigation.....	2-10
2.3.1 Evaluation of Existing Wells.....	2-10
2.3.2 Monitoring Well Installation.....	2-10
2.3.3 Downhole Geophysical Logging.....	2-12
2.3.4 In-Situ Hydraulic Conductivity Testing.....	2-13
2.3.5 Groundwater Level Measurements.....	2-13
2.4 Hydrologic Evaluation.....	2-14
2.4.1 Surface Water Flow Measurements.....	2-14
2.3.2 Surface Water Level Measurements.....	2-14

2.5 Soil/Sediment Evaluation.....	2-14
2.6 Air Evaluation.....	2-15
2.7 Human Population Evaluation.....	2-15
2.8 Ecological Evaluation.....	2-15
2.9 Potential Migration Pathway/Contaminant Characterization.....	2-16
2.9.1 Groundwater.....	2-16
2.9.2 Private and Municipal Water Supply Wells.....	2-17
2.9.3 Surface Water Sampling.....	2-18
2.9.4 Sediment and Soil Sampling.....	2-18

3

SITE PHYSICAL CHARACTERISTICS.....	3-1
3.1 Landfill Characteristics.....	3-1
3.1.1 Landfill Cover Physical Observations and Cover Evaluation.....	3-1
3.1.2 Landfill Structure/Refuse Characteristics.....	3-3
3.1.3 On-Site Landfill Gas Assessment.....	3-4
3.2 Climate.....	3-5
3.3 Physiography.....	3-5
3.4 Surface Hydrology.....	3-5
3.5 Surface Soils.....	3-7
3.6 Regional Hydrogeologic Setting.....	3-8
3.6.1 Regional Geology.....	3-8
3.6.2 Regional Hydrogeology.....	3-10
3.7 Site Hydrogeologic Setting.....	3-11
3.7.1 Site Geology.....	3-11
3.7.2 Site Specific Hydrogeology.....	3-14

4

NATURE AND EXTENT OF CONTAMINATION.....	4-1
4.1 Summary.....	4-1
4.2 Sampling and Analysis.....	4-2
4.3 Site Source Areas and Potential Contaminant Pathways.....	4-3
4.4 Contaminant Groupings.....	4-4
4.4.1 Volatile Organic Compounds.....	4-5
4.4.2 Semivolatile Organic Compounds.....	4-6
4.5 Compound Concentration Comparisons.....	4-6
4.5.1 Applicable Regulations.....	4-6
4.5.2 Background Evaluation.....	4-6
4.6 Source Characterization.....	4-9
4.6.1 Landfill Gas.....	4-9
4.6.2 Leachate.....	4-9

4.7 Media Characterization.....	4-11
4.7.1 Surface Soils.....	4-11
4.7.2 Groundwater.....	4-12
4.7.3 Village of Antioch Water Supply Wells.....	4-17
4.7.4 Private Residence Wells.....	4-18
4.7.5 Surface Water.....	4-19

5

CONTAMINANT FATE AND TRANSPORT.....	5-1
5.1 Summary of Findings.....	5-1
5.2 Physical/Chemical Attenuation Mechanisms.....	5-2
5.2.1 Dilution/Attenuation.....	5-2
5.2.2 Adsorption/Desorption.....	5-2
5.2.3 Biodegradation.....	5-4
5.2.4 Oxidation/Reduction.....	5-4
5.2.5 Volatilization.....	5-5
5.2.6 Precipitation.....	5-5
5.2.7 Hydrolysis.....	5-5
5.3 Potential Migration Pathways.....	5-5
5.3.1 Groundwater/Private Wells.....	5-5
5.3.2 Surface Water.....	5-7
5.3.3 Surface Soils.....	5-7
5.3.4 Air (Landfill Gas).....	5-7

6

CONCLUSIONS.....	6-1
------------------	-----

7

REFERENCES.....	7-1
-----------------	-----

LIST OF TABLES

Table 1-1	List of Acronyms and Abbreviations
Table 3-1	Soil Testing Results from Landfill Cap Evaluation
Table 3-2	Results of Boutwell Conductivity Testing of Clay Cap
Table 3-3	Landfill Cap Thickness and Vertical Extent of Refuse
Table 3-4	Landfill Gas Perimeter Probe Field Screening Results
Table 3-5	Sequoit Creek Staff Gage and Stand Pipe Water Levels
Table 3-6	Sequoit Creek Flow Measurements
Table 3-7	Geotechnical Laboratory Results
Table 3-8	Summary of Soil Testing Results - Previous Investigations
Table 3-9	Groundwater Elevations
Table 3-10	In-Situ Hydraulic Conductivity Results
Table 3-11	Summary of Slug Test Data Analysis Conducted by U.S. EPA FIT
Table 3-12	Vertical Groundwater Gradients
Table 3-13	Leachate Elevations
Table 4-1	Regulatory Limits
Table 4-2	Summary of Background Metals and Indicator Results
Table 4-3	Summary of Landfill Gas Results
Table 4-4	Summary of Volatile Organic Compounds in Groundwater, Surface Water, Surface Soils, and Leachate
Table 4-5	Summary of Historical Monitoring Well VOC Data
Table 4-6	Summary of Semivolatile Organic Compounds in Groundwater, Surface Water, Surface Soils, and Leachate
Table 4-7	Summary of Metals in Groundwater, Surface Water, Surface Soils, and Leachate
Table 4-8	Summary of Groundwater/Leachate Quality Indicator Results
Table 4-9	Summary of Chemical Constituents Detected at Village of Antioch Water Supply Wells and Private Residence Wells
Table 4-10	Summary of Historical Data for VOCs Detected in Village of Antioch Water Supply Well No. 4
Table 5-1	Summary of Physical and Chemical Properties of Compounds Detected at H.O.D. Landfill

LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Village Water Supply Well Location Map
Figure 3	Private Water Supply Well Sampling Locations
Figure 4	Wetlands Inventory Map
Figure 5	Stratigraphic Column For Northeastern Illinois
Figure 6	Pleistocene Stratigraphic Column For Chicago Area
Figure 7	Sequoit Acres Industrial Park Map
Figure 8	Filled Areas In Industrial Park Map
Figure 9	Surficial Soils Map
Figure 10	Surface Water and Surface Soil Sampling Location Map
Figure 11	Leachate Piezometers/Gas Well Location Map
Figure 12	Geologic Cross Section Location Map
Figure 13	Geologic Cross Section A-A'
Figure 14	Geologic Cross Section B-B'
Figure 15	Geologic Cross Section C-C'

LIST OF DRAWINGS

Drawing 10010201-F1	Site Features Map
Drawing 10010201-F2	Monitoring Well, Soil Boring, And Leachate Piezometer Location Map
Drawing 10010201-F3	Regional Geologic Cross Section
Drawing 10010201-F4	Surficial Sand Isopach Map
Drawing 10010201-F5	Clay-Rich Diamict Isopach Map
Drawing 10010201-F6	Surficial Sand Water Table Map (June 8 and 9, 1993)
Drawing 10010201-F7	Piezometric Surface Map (June 8 and 9, 1993)
Drawing 10010201-F9	Groundwater VOC Concentrations

VOLUME II

LIST OF APPENDICES

Appendix A	Test Pit Logs
Appendix B	Leachate Piezometer/Landfill Gas Well Boring Logs and Well Construction Details
Appendix C	Perimeter Gas Probe Boring Logs and Probe Construction Details
Appendix D	Geophysical Logs
Appendix E	Landfill Boring Logs
Appendix F	Geotechnical Laboratory Data
Appendix G	Summary of Environmental History of Sequoit Acres Industrial Park Through 1989
Appendix H	Groundwater Monitoring Well Boring Logs and Well Construction Details
Appendix I	Monitoring Well Development Data
Appendix J	Results of In-Field Hydraulic Conductivity Testing
Appendix K	Groundwater Sampling Field Parameter Results
Appendix L	Meteorological Data

VOLUME III

Appendix M	Village and Private Residence Water Supply Well Logs
	M1 Municipal Well Construction Information
	M2 Private Well Logs
Appendix N	Results of Landfill Cap Evaluation
	N1 Geotechnical Analytical Results
	N2 Boutwell Test Data
Appendix O	Village of Antioch Water Supply Well Pumping Records
Appendix P	Analytical Laboratory Results
	P1 Data Quality Summary, Data Qualifier Definitions, and Analytical Data Results
	P2 Landfill Gas VOCs
	P3 Leachate VOCs
	P4 Leachate SVOCs
	P5 Leachate Pesticides/PCBs
	P6 Leachate Indicators and Metals
	P7 Leachate Tentatively Identified Compounds (TICs)
	P8 Surface Soils VOCs
	P9 Surface Soils SVOCs
	P10 Surface Soils Pesticides/PCBs
	P11 Surface Soils Metals
	P12 Surface Soils Tentatively Identified Compounds (TICs)
	P13 Groundwater VOCs
	P14 Groundwater SVOCs
	P15 Groundwater Pesticides/PCBs
	P16 Groundwater Indicators and Metals
	P17 Groundwater Tentatively Identified Compounds (TICs)
	P18 Private Water Supply VOCs
	P19 Private Water Supply SVOCs
	P20 Private Water Supply Pesticides/PCBs
	P21 Private Water Supply Metals
	P22 Surface Water VOCs
	P23 Surface Water SVOCs
	P24 Surface Water Pesticides/PCBs
	P25 Surface Water Indicators and Metals
	P26 Surface Water Tentatively Identified Compounds (TICs)

A

TEST PIT LOGS

Test Pit 1

- A- 0 to 2 inches; very dark gray (10YR 3/1) silt loam (ML); moderate fine granular structure; many fine roots; clear smooth boundary.
- B- 2 to 12 inches; light brownish gray (10YR 6/2) clay (CL); weak coarse angular blocky structure; many fine roots; clear wavy boundary.
- C- 12 to 24 inches; gray (10YR 5/1) silty clay (CL); weak very coarse angular blocky structure; few fine roots; clear wavy boundary.
- D- 24 to 31 inches; gray (10YR 5/1) silty clay (CL); massive structure; no roots; abrupt wavy boundary.
- E- 31 to 43 inches; gray (10YR 5/1) and brownish yellow (10YR 6/6) silt loam (ML); few fine distinct mottles; structureless; few fine roots; clear wavy boundary.
- F- 43 to 50 inches; very dark gray (10YR 3/1) loam (ML); weak medium angular blocky structure; no roots; abrupt wavy boundary.
- G- 50 to 53 inches; white chalky material with pottery fragments; abrupt wavy boundary.
- H- 53 to 80 inches; dark brown grading to black clay loam (ML); structureless; abrupt wavy boundary.

REFUSE 80+ inches

Vegetative cover-100 percent, grasses

Root penetration-24 inches

No fissures or deformities

Test Pit 2

- A- 0 to 14 inches; black (10YR 2/1) silty clay loam (ML-CL); moderate fine granular structure; many fine roots; clear wavy boundary.
- B- 14 to 23 inches; gray (10YR 5/1) and yellowish brown (10YR 5/6) silty clay (CL); weak medium angular blocky structure; common fine roots; clear wavy boundary.
- C- 23 to 34 inches; gray (10YR 5/1) and yellowish brown (10YR 5/6) silty clay (CL); no structure; few fine roots; clear wavy boundary.
- D- 34 to 40 inches; brownish yellow (10YR 6/6) loam (ML); few fine distinct gray (10YR 6/1) and yellowish red (5YR 5/8) mottles; massive structure; no roots; clear wavy boundary.
- E- 40 to 50 inches; very dark gray (10YR 3/1) loam (ML); no structure; common fine roots; clear wavy boundary.
- F- 50 to 70 inches; gray (10YR 5/1) silt loam (ML); massive structure; no roots; abrupt wavy boundary.

REFUSE 70+ inches

Vegetative cover-100 percent, grasses

Root penetration-34 inches

No fissures or deformities

Test Pit 3

- A- 0 to 8 inches; very dark gray (5Y 3/1) silty clay loam (ML-MC); structureless; many fine roots; clear wavy boundary.
- B- 8 to 15 inches; very dark gray (10YR 3/1) loam (ML); moderate fine granular structure; many fine roots; clear wavy boundary.
- C- 15 to 26 inches; gray (10YR 5/1) clay loam (MC-ML) and clay (CL); moderate and weak medium platy structure; common fine roots; clear wavy boundary.
- D- 26 to 36 inches; gray (10YR 5/1) and yellowish brown (10YR 5/6) clay (CL); structureless; no roots; clear wavy boundary.
- E- 36 to 43 inches; very dark gray (10YR 3/1) silt loam (ML); weak fine granular structure; common fine roots; clear wavy boundary.
- F- 43 to 56 inches; pale brown (10YR 6/3) clay (CL) with many medium distinct gray (10YR 5/1) mottles; massive structure; no roots; abrupt wavy boundary.
- G- 56 to 87 inches; black (10YR 2/1) silt loam (ML); structureless; no roots; abrupt wavy boundary.

REFUSE 87+ inches.

Vegetative cover- 50 to 100 percent; grasses,
Queen Anne's Lace
Root penetration-26 inches
No fissures or deformities

Test Pit 4

- A- 0 to 3 inches; very dark gray (10YR 3/1) silt loam (ML); moderate fine granular structure; common fine roots; gradual wavy boundary.
- B- 3 to 17 inches; brown (10YR 5/3) silt loam (ML) and silty clay loam (ML-CL); common medium distinct yellowish brown (10YR 5/6) and gray (10YR 5/1) mottles; weak and moderate, fine and medium, angular blocky structure; few fine roots; gradual wavy boundary.
- C- 17 to 30 inches; gray (10YR 5/1) silty clay (CL); few fine distinct yellowish red (5YR 5/8) mottles; weak very coarse angular blocky structure; few fine roots; common distinct brown (10YR 5/3) clay films on faces of peds; gradual wavy boundary.
- D- 30 to 41 inches; gray (10YR 5/1) and brown (10YR 5/3) silty clay (CL); few fine yellowish brown (10YR 5/6) mottles; weak coarse angular blocky structure; common fine roots; gradual wavy boundary; about 3 percent gravel.
- E- 41 to 55 inches; gray (10YR 5/1) and brown (10YR 5/3) silty clay (CL); few fine yellowish brown (10YR 5/6) mottles; structureless; no roots; clear wavy boundary; about 3 percent gravel.
- F- 55 to 62 inches; black (10YR 2/1) silt loam (ML), structureless, no roots; abrupt wavy boundary.

REFUSE 62+ inches

Vegetative cover-100 percent, grasses
Root penetration-41 inches
No fissures or deformities

Test Pit 5

- A- 0 to 8 inches; dark gray (10YR 4/1) silt loam (ML); moderate fine granular structure; many fine roots; clear smooth boundary.
- B - 8 to 17 inches; gray (10YR 5/1) silty clay (CL); moderate medium angular blocky and strong fine angular blocky structure; common fine roots; clear wavy boundary.
- C- 17 to 20 inches; brown (10YR 5/3) and gray (10YR 5/1) silty clay (CL); weak fine and medium angular blocky structure; few fine roots; clear wavy boundary.
- D- 20 to 26 inches; gray (10YR 5/1) silt loam (ML); weak medium blocky structure; few fine roots; about 3 percent coarse sand particles; gradual wavy boundary.
- E- 26 to 31 inches; gray (10YR 5/1) silt loam (ML); weak medium platy structure few fine roots; common distinct yellowish brown (10YR 5/6) clay films on faces of peds; clear wavy boundary.
- F- 31 to 40 inches; very dark gray (10YR 3/1) loam (ML); structureless; no roots; abrupt wavy boundary.
- G- 40 to 49 inches; white chalky material with pottery fragments; abrupt wavy boundary.

REFUSE 49+ inches.

Vegetative cover-75 percent, grasses
Root penetration-31 inches
No fissures or deformities

Test Pit 6

- A- 0 to 7 inches; very dark gray (7.5YR 3/1) loam (ML); moderate fine granular structure; common fine roots; clear wavy boundary.
- B- 7 to 20 inches; brown (10YR 5/3) and gray (10YR 5/1) clay loam (ML-CL); few medium distinct reddish yellow (7.5YR 6/6) mottles; weak fine subangular blocky structure; few fine roots; clear wavy boundary.
- C- 20 to 41 inches; light yellowish brown (10YR 6/4) silty clay loam (ML-CL); few medium faint brownish yellow (10YR 6/6) and few medium distinct light gray (10YR 7/1) mottles; weak fine and medium subangular blocky structure; no roots; clear wavy boundary.
- D- 41 to 65 inches; gray (10YR 5/1) silty clay (CL); weak and moderate medium and coarse angular blocky structure; no roots; abrupt wavy boundary.

REFUSE 65+ inches.

Vegetative cover-5 to 75 percent; grasses, clover, chicory, Queen Anne's Lace
Root penetration-20 inches
No fissures or deformities

Test Pit 7

- A- 0 to 8 inches; black (2.5Y 2.5/1) silt loam (ML); moderate fine granular structure; common fine roots; abrupt wavy boundary.
- B- 8 to 35 inches; brown (10YR 4/3) clay loam (ML-CL); few medium faint strong brown (7.5YR 5/6) and many coarse distinct gray (7.5YR 5/1) mottles; moderate medium subangular blocky structure; few fine roots; clear wavy boundary.
- C- 35 to 47 inches; brown (10YR 5/3) clay (CL); common medium distinct strong brown (7.5YR 5/6) mottles; massive structure; no roots; clear wavy boundary.
- D- 47 to 56 inches; light yellowish brown (2.5Y 6/4) and gray (7.5YR 6/1) silt loam (ML); massive structure; no roots; clear wavy boundary.
- E- 56 to 60 inches; black (N2.5/)clay (CL); common coarse distinct strong brown (7.5YR 5/6) mottles; massive structure; no roots; abrupt wavy boundary.

REFUSE 60+ inches.

Vegetative cover-100 percent, grasses
Root penetration-35 inches
No fissures or deformities

Test Pit 8

- A- 0 to 10 inches; black (10YR 2/1) silt loam (ML); moderate fine granular structure; common fine roots; clear wavy boundary.
- B- 10 to 33 inches; stratified brown and dark grayish brown sand (SP), loam (ML), sandy loam (SM), silty clay (CL), and clay (CL); moderate medium angular blocky and moderate fine granular structure; few fine roots; clear wavy boundary.
- C- 33 to 56 inches; yellow (2.5Y 7/6) and light gray (2.5Y 7/1) clay (CL), silty clay (CL), and silty clay loam (ML-CL); structureless; no roots; common distinct brownish yellow (10YR 6/6) clay films on faces of peds; clear wavy boundary.
- D- 56 to 82 inches; gray (10YR 5/1) silty clay (CL); massive structure; no roots; abrupt wavy boundary.

REFUSE 82+ inches.

Vegetative cover-100 percent, grasses
Root penetration-33 inches
No fissures or deformities

Test Pit 9

- A- 0 to 6 inches; very dark gray (10YR 3/1) loam (ML); moderate fine granular structure; common fine roots; clear wavy boundary.
- B- 6 to 14 inches; yellowish brown (10YR 5/6) loamy sand (SM); weak medium angular blocky structure; few fine roots; clear wavy boundary.
- C- 14 to 21 inches; gray (10YR 5/1) silty clay (CL); strong small and medium angular blocky structure; few fine roots; common faint dark yellowish brown (10YR 4/4) clay films on faces of peds; gradual wavy boundary.
- D- 21 to 29 inches; gray (10YR 5/1) silty clay (CL); strong medium angular blocky structure; no roots; common faint dark yellowish brown (10YR 4/4) clay films on faces of peds; about 3 percent gravel; clear wavy boundary.
- E- 29 to 84 inches; gray (10YR 5/1) silty clay (CL); massive structure; no roots; about 3 percent gravel; abrupt wavy boundary.

REFUSE 84+ inches.

Vegetative cover-100 percent, grasses
Root penetration-21 inches
No fissures or deformities

Test Pit 10

- A- 0-9 inches; black (10YR 2/1) silt loam (ML); moderate fine granular structure; many fine roots; clear wavy boundary.
- B- 9 to 22 inches; gray (10YR 5/1) silty clay (CL); few medium faint brownish yellow (10YR 6/6) mottles; moderate medium angular blocky structure; few fine roots; gradual wavy boundary.
- C- 22 to 30 inches; gray (10YR 5/1) silty clay (CL); few medium faint brownish yellow (10YR 6/6) mottles; weak medium columnar structure; few fine roots; common faint brown (10YR 5/3) clay films on faces of peds; clear wavy boundary.
- D- 30 to 62 inches; gray (10YR 5/1) silty clay (CL); massive structure; no roots; common faint light brownish gray (10YR 6/2) clay films on faces of peds; abrupt wavy boundary.

REFUSE 62+ inches.

Vegetative cover-100 percent; grasses.
Queen Anne's Lace
Root penetration-30 inches
No fissures or deformities

B

**LEACHATE PIEZOMETER/LANDFILL
GAS WELL BORING LOGS AND
WELL CONSTRUCTION DETAILS**

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10 1/4" ID HSA	BORING NO. LP1
		SHEET 1 OF 1
	SAMPLING METHOD: 2" ID SPLIT SPOON	DRILLING START TIME: _____ FINISH TIME: _____
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	DATE: 4/27/93 DATE: 4/27/93
NORTHING 2116410.7 EASTING 1050909.7	CASING DEPTH	
DATUM _____ ELEVATION 775.6	SURFACE CONDITIONS GRASS COVERED LANDFILL CAP	
DRILL RIG CME 75		
ANGLE Vertical BEARING -----		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS									
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS					
771.6				FILL: Brown Clay Cap													
770.6				Black Clay Cap Material													
				Refuse													
10	3 12 13 15	33	1	FILL: Refuse - Paper, Metal, Plastic, Cloth, Etc.	SS												
15	5 7 4 2	100	2	Wet Black Muck and Garbage at Approximately 14' 15% LEL Pulling Center Bit Refuse - Metal Plastic, etc.	SS												
20	9 9 9 10	4	3	Refuse Mostly Wood and Black Wet Material	SS												
752.6				Cuttings Changed Color From Black to Brown at Approximately 23 feet													
25			4	1" Fine to Coarse Sand Layer at 25', Brown Silty CLAY (CL), Silty Lenses Present 1/8 - 1/4" Trace Fine to Coarse Sand	SS												
748.6	3 4 6 5	46	5	Gray Clayey SILT (ML) Trace Fine to Coarse Sand	SS												
746.6				End of Boring at 29 Feet Leachate Piezometer Set at 20.31 Ft PID = None Detected													

LOGGED BY <u>SJC</u>	DRILLING CONTR <u>E & F</u>
DATE <u>9/17/93</u>	CHK'D BY <u>DAP</u>
	<u>CHAS. MARKGRAF</u>

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10 1/4" ID HSA	BORING NO. LP2
	SAMPLING METHOD: 3" OD SPLIT SPOON	SHEET 1 OF 2
		DRILLING START TIME: _____ FINISH TIME: _____
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W	WATER LEVEL TIME: _____	
NORTHING 2116428.7 EASTING 1051349.0	DATE: _____	DATE: _____
DATUM _____ ELEVATION 785.8	CASING DEPTH: _____	4/29/93 4/30/93
DRILL RIG CME 75	SURFACE CONDITIONS GRASS COVERED LANDFILL CAP	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE _____	FT-LBS _____	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
781.8				Grass Surface Brown CLAY (CL) Trace to Some Gravel, Landfill Cap Material										
5				Black Clay and Refuse <i>Blind Drill to 20 Feet</i>										
10														
15														
20	4 5 6 6	50	1	Refuse	SS									
25	60/4 in.	20	2	Refuse	SS									
30	100/14"	25	3	Refuse	SS									
35	12 11 13 14	50	4	Refuse	SS									
745.8														

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93 CHK'D BY DAP	BRANDON POWERS ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
Illinois

SHEET
2 OF 2

BORING NO.
LP2

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS													
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS									
741.8 45 50 55 60 65 70 75 80 85 90 95	15 11	50	█	5 Gray Silty CLAY (CL). Trace Gravel	SS																
	13 14																				
	7 10	100		6		SS															
	13 15																				
				End of Boring at 44 Feet Leachate Piezometer Set at 35 Feet PID = None Detected																	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION: **H.O.D. Landfill - Antioch, Illinois**

DRILLING METHOD: **10 1/4" ID HSA**

BORING NO. _____

LP3

SHEET _____

SAMPLING METHOD: **2" OD SPLIT SPOON 3" OD**

1 OF **1**

SPLIT SPOON (30 - 32 FT)

DRILLING
START FINISH

WATER LEVEL

TIME TIME

TIME

DATE

DATE DATE

CASING DEPTH

4/28/93 4/28/93

SURFACE CONDITIONS

GRASS COVERED LANDFILL CAP

BORING LOCATION:
SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/V
NORTHING **2116428.7** EASTING **1050318.9**
DATUM _____ ELEVATION **778.1**
DRILL RIG **CME 75**

ANGLE **Vertical** BEARING **-----**
SAMPLE HAMMER TORQUE **FT-LBS**

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS							
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS			
773.1	-	50	[Hatched Pattern]	FILL: Blind Drill to 15 Feet Brown Cap Clay to Approximately 5 Feet then Black Clay and Little Refuse to Approximately 8 Feet then more Refuse and Little Clay to 10 Feet											
			[Hatched Pattern]	FILL: Black Clay and Refuse											
			[Hatched Pattern]	Refuse - Metal, Wood, Plastic, Paper, etc. and Black Clay											
			[Hatched Pattern]	Brown Clay and Black Refuse - Wood	SS										
			[Hatched Pattern]	Black Wet Refuse - Paper and Wood 30 - 50% LEL from Auger Head and After Collected Sample	SS										
			[Hatched Pattern]	Brown Clay and Black Refuse - Wood	SS										
			[Hatched Pattern]	Gray Clayey SILT (ML)	SS										
			[Hatched Pattern]	Fine to Coarse SAND and Fine GRAVEL (SP/GP), Clay Lenses at Approximately 31.3' 15-50% LEL From Auger Head	SS										
			[Hatched Pattern]	Fine to Coarse SAND (SP) Grading to Fine to Medium Sand 5 - 15% LEL in Augers	SS										
			[Hatched Pattern]	End of Boring at 37 Feet Leachate Piezometer Set at 25.5 Feet PID = None Detected											

LOGGED BY **SJC**

DATE **9/18/93** CHK'D BY **DAP**


DRILLING CONTR **E & F**
CHAS. MARKGRAF

ID: WMT

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10 1/4" ID HSA	BORING NO. LP4
SAMPLING METHOD: 3" SPLIT SPOON		SHEET 1 OF 2
DRILLING		
WATER LEVEL		START TIME
TIME		12:30
DATE		14:00
CASING DEPTH:		DATE
		5/3/93
DRILL RIG CME 75		FINISH DATE 5/4/93
SURFACE CONDITIONS GRASS COVERED LANDFILL CAP		
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS



LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
BRANDON POWERS	
ID: WM1	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**

SHEET

BORING NO.

Illinois

2 OF 2

LP4

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS
<div style="text-align: right; margin-right: 5px;">742.9</div> <div style="text-align: center;">45</div> <div style="text-align: center;">50</div> <div style="text-align: center;">55</div> <div style="text-align: center;">60</div> <div style="text-align: center;">65</div> <div style="text-align: center;">70</div> <div style="text-align: center;">75</div> <div style="text-align: center;">80</div> <div style="text-align: center;">85</div> <div style="text-align: center;">90</div> <div style="text-align: center;">95</div>	<div style="text-align: center;">58 11 14</div> <div style="text-align: center;">67 12 13</div>	<div style="text-align: center;">100</div> <div style="text-align: center;">100</div>	<div style="text-align: center;">6</div> <div style="text-align: center;">7</div>	<p style="text-align: center;">Gray Silty CLAY (CL)</p>	<div style="text-align: center;">SS</div> <div style="text-align: center;">SS</div>							<div style="text-align: center;">-</div> <div style="text-align: center;">-</div>
				<p>End of Boring at 46 Feet Leachate Piezometer Set at 39 Feet</p>								

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP5
		SHEET 1 OF 2
	SAMPLING METHOD: 3" SPLIT SPOON	DRILLING START TIME: 7:30 FINISH TIME: 12:00
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	CASING DEPTH: 4/20/93 4/21/93
NORTHING 2116230.0 EASTING 1051719.6	DATE: _____	DATE: _____
DATUM _____ ELEVATION 796.6	SURFACE CONDITIONS _____	
DRILL RIG CME 75		
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE _____ FT-LBS _____		

DEPTH IN FEET (ELEVATION)	BLOWS/G IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
792.1				Grass Surface Lt. Brown Clay (CL) Some Silt and Gravel										
5				Dark Gray Silty Organic Clay with Refuse										
10														
15														
20														
25														
30	5 10 12 7	50	1	Refuse	SS									
35	100/6*	25	2		SS									
	10 12 9 11	75	3		SS									

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
	BRANDON POWERS
	ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP6
	SAMPLING METHOD: 3" SPLIT SPOON	SHEET 1 OF 1
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W	WATER LEVEL TIME 16:00	DRILLING START TIME 12:00
NCRTHING 2115990.2 EASTING 1051732.1	DATE	DATE
DATUM ELEVATION 794.6	CASING DEPTH	4/14/93 4/16/93
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical BEARING -----		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
790.1				Grass Surface Light Brown Silty Clay (CL)										
5				Light Gray to Dark Gray Silty Organic Clay with Refuse										
10														
15														
20														
25	35 177	30	1		SS									
30	14 17 58	60	2	Refuse and Black Clay	SS									
35	21 7 32		3		SS									
	43 42		4		SS									
40	100/7"		5	Refuse	SS									
754.6	8 13 19 12	15	6	Gray Silty CLAY (CL)	SS									
752.6				End of Boring at 42 Feet Leachate Piezometer Set at 36.5 Feet										

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/18/93	CHK'D BY DAP
BRANDON POWERS	
ID: WM1	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP7
	SAMPLING METHOD: 3" SPLIT SPOON	SHEET 1 OF 2
		DRILLING START TIME: 18:00 FINISH TIME: 12:30
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9, T 46 N, R 10 E/W	WATER LEVEL TIME	DATE
NORTHING 2116197.8	EASTING 1052105.4	DATE
DATUM	ELEVATION 794.7	CASING DEPTH: 4/27/93 4/28/93
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOBS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOBS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
5	789.7			Grass Surface Brown Silty Clay, Trace Gravel										
				Refuse										
30	100/7	25	█	1	SS									
35	56 18 20	30	█	2	SS									

LOGGED BY PMS	DRILLING CONTR E & F	
DATE 9/17/93	CHK'D BY DAP	BRANDON POWERS
		ID: WMI

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP8
		SHEET 1 OF 2
	SAMPLING METHOD: 3" SPLIT SPOON	DRILLING START TIME: 14:00 FINISH TIME: 17:00
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9, T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	DATE: 4/23/93
NORTHING 2116218.6	EASTING 1052519.4	DATE: 4/27/93
DATUM	ELEVATION 793.5	CASING DEPTH
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOBS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOBS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
5				Grass Surface Brown Silty Clay with Trace Gravel										
786.5				Refuse with Black Clay										
30	8 8 22 17	50	1	Refuse	SS									
35	17 19 10 21	55	2	Refuse	SS									

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
BRANDON POWERS	
ID: WM1	ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**

SHEET

BORING NO.

Illinois

2 OF 2

LP8

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
45	10 12 15 15	75		3 Refuse	SS									
50	11 13 14 12	75		4 Refuse	SS									
55	15 16 17 9	100		5 Refuse	SS									
60	100/14"	55		6 Refuse	SS									
65	5 7 7 13	80		7 Refuse	SS									
70	8 10 12 15	40		8 Refuse	SS									
75	723.0 8 9 16 17	100		9 Gray Silty CLAY (CL), Trace Fine to Coarse Sand	SS									
75	718.5 7 8 11 14	100		10	SS									
				End of Boring at 75 Feet Leachate Piezometer Set at 70 Feet										

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP9
		SHEET 1 OF 2
	SAMPLING METHOD: 3" SPLIT SPOON	DRILLING START TIME: 14:00 FINISH TIME: 12:00
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9 , T 46 N, R 10 E/W	DATE: 4/21/93	DATE: 4/23/93
NORTHING 2116220.4 EASTING 1052769.9	CASING DEPTH	
DATUM	ELEVATION 785.8	
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
5				Grass Surface Light Brown Silty Clay with Trace Fine to Coarse Sand										
777.8				Black Clay and Refuse										
10														
15														
20														
25														
30	11/10/ 60/1"	50	1	Refuse	SS									
35	5 7 11 21	55	2	Refuse	SS									
	5 7 8 22	50	3	Refuse	SS									

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
	BRANDON POWERS
	ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois		DRILLING METHOD: 10 1/4" ID HSA	BORING NO. LP10
		SAMPLING METHOD: 2" OD SPLIT SPOON 3" OD SPLIT SPOON (30-32 FT)	SHEET 1 OF 1
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W		WATER LEVEL	DRILLING START TIME
NORTHING 2115810.4	EASTING 1050919.8	DATE	DATE
DATUM	ELEVATION 781.1	CASING DEPTH	4/27/93 4/27/93
DRILL RIG	SURFACE CONDITIONS GRASS COVERED LANDFILL CAP		
ANGLE Vertical	BEARING -----		
SAMPLE HAMMER TORQUE	FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS									
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS					
5				FILL: Brown CLAY Cap Material													
10				FILL: Black Clay and Refuse													
20				Refuse		SS											
25				Clay Cuttings at Approximately 23 - 24'													
25	3 3 4 5	4		Refuse - Pushed 2" Spoon then 3" Spoon to Try to Get Better Recovery, No Recovery on 3" Spoon		SS											
30	6 6 8 8	58		Gray Silty CLAY (CL) Trace Fine to Coarse Sand		SS											
35				PID = None Detected End of Boring at 32 Feet Leachate Well Set at 23 Feet PID = None Detected													

LOGGED BY SJC	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
	DAVID MASKE

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
Illinois

DRILLING METHOD: **10.25" ID HSA**

BORING NO. **LP11**

SAMPLING METHOD: **2" SPLIT SPOON**

SHEET **1** OF **1**
 DRILLING

BORING LOCATION:

SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W
 NORTHING **2115807.1** EASTING **1051321.8**
 DATUM ELEVATION **787.8**

WATER LEVEL

TIME

DATE

CASING DEPTH

START FINISH
 TIME TIME

DATE DATE

4/8/93 4/12/93

DRILL RIG **CME 75**

SURFACE CONDITIONS

ANGLE **Vertical** BEARING **-----**

SAMPLE HAMMER TORQUE FT-LBS

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS										
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS						
0				Grassy Surface Black Silty Clay Topsoil														
5				FILL: Light Brown Silty Clay, Trace Fine to Coarse Sand and Fine Gravel														
7.8				778.8														
10				Black Clayey Sandy Refuse														
20	3 15 17 19	24	1	Refuse	SS													
25	100/16"	0	2	Refuse	SS													
30	10 12 7 7	12	3	Black Clayey Soil and Refuse	SS													
35	7 10 4 10	18	4	Black Organic Clay and PEAT (OH)	SS													
				End of Boring at 35 Feet Leachate Piezometer Set at 29.2 Feet														

LOGGED BY **PMS**

DRILLING CONTR **E & F**

DATE **9/17/93**

CHK'D BY **DAP**

BRANDON POWERS

ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois		DRILLING METHOD: 10.25" ID HSA	BORING NO. LP12	
		SHEET 1 OF 1		
		SAMPLING METHOD: 2" SPLIT SPOON	DRILLING START TIME: FINISH TIME:	
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W		WATER LEVEL TIME	DATE	
NORTHING 2115515.5	EASTING 1051138.4	DATE	DATE	DATE
DATUM	ELEVATION 782.6	CASING DEPTH	4/7/93	4/8/93
DRILL RIG CME 75	SURFACE CONDITIONS			
ANGLE Vertical	BEARING			
SAMPLE HAMMER TORQUE FT-LBS				

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS											
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS							
				Grass Surface Black Silty Clay Topsoil															
5				Brown Silty Clay Cap. Trace Sand and Gravel															
				Black Silty/Sandy Fill															
				Refuse															
25				Gray Silty Fine to Medium SAND (SM)															
				End of Boring at 27 Feet Leachate Piezometer Set at 22.5 Feet															

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
BRANDON POWERS	
ID: WM1	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP13
	SAMPLING METHOD: 2" SPLIT SPOON	SHEET 1 OF 1
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W	WATER LEVEL TIME	DRILLING START TIME FINISH TIME
NORTHING 2115448.4 EASTING 1050899.8	DATE	DATE DATE
DATUM ELEVATION 779.0	CASING DEPTH:	4/13/93 4/13/93
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS									
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS					
				Grass Surface FILL: Black to Dark Brown Silty Clay Topsoil to 8"													
5				Brown Fine to Coarse Clayey Sand to Sandy Clay													
				Black Clay Mixed with Refuse													
				Approximate Base of Refuse													
20	2557	18	1	Gray Fine to Coarse Silty SAND (SM), Trace to Some Clay	SS												
	2547	18	2		SS												
25				End of Boring at 24 Feet Leachate Piezometer Set at 17 Feet													

LOGGED BY PMS	DRILLING CONTR E & F
DATE 9/17/93 CHK'D BY DAP	BRANDON POWERS ID: WMI

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 10.25" ID HSA	BORING NO. LP14
	SAMPLING METHOD: 2" SPLIT SPOON	SHEET 1 OF 1
		DRILLING START TIME: FINISH TIME:
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W	WATER LEVEL TIME	DATE: DATE
NORTHING 2115474.5 EASTING 1051389.5	DATE	4/13/93 4/13/93
DATUM ELEVATION 781.7	CASING DEPTH	
DRILL RIG CME 75	SURFACE CONDITIONS	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS										
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS						
777.2				Grass Surface Black Silty Clayey Topsoil Brown Silty/Sandy Clay														
5				Refuse														
	5 12 11 13	6	1	Refuse	SS													
20	4 18 7 10	9	2	Refuse	SS													
758.2	2 3 2 2	12	3	Base of Refuse	SS													
	2 4 9 6	9	4	Light Gray Silty Fine SAND (SM)	SS													
754.7				Native Soil														
				End of Boring at 27 Feet Leachate Piezometer Set at 22.5 Feet														


LOGGED BY PMS	DRILLING CONTR PMS
DATE 9/17/93	CHK'D BY DAP
	BRANDON POWERS
	ID: WM1



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP1

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/28/93
Contractor	E & F
Coordinates	2116410.7N, 1050909.7 E



1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYDRATED CHIPS
CONCRETE _____
3. HYDRATED BENTONITE
CHIPS, AND FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 10.44 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP

ELEVATION 778.46 ft

STICK-UP 2.86 ft

GROUND SURFACE ELEVATION 775.6 ft

DEPTH BELOW GROUND SURFACE _____

TOP OF FINE SAND 6.5 ft
ELEVATION 769.1 ft

TOP OF PEA GRAVEL 7 ft
ELEVATION 768.6 ft

TOP OF SCREEN 9.87 ft
ELEVATION 765.73 ft

BOTTOM OF SCREEN 20.31 ft
ELEVATION 755.29 ft

END OF BORING 29 ft
ELEVATION 746.6 ft



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP2

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/30/93
Contractor	E & F
Coordinates	2116428.7N, 1051349E

ELEVATION 787.8 ft

STICK-UP 2.3 ft

ROUND SURFACE ELEVATION 785.5 ft

DEPTH BELOW GROUND SURFACE


TOP OF FINE SAND 7.4 ft
ELEVATION 778.1 ft

TOP OF PEA GRAVEL 8.5 ft
ELEVATION 777 ft

TOP OF SCREEN 9.7 ft
ELEVATION 775.8 ft

BOTTOM OF SCREEN 35 ft
ELEVATION 750.5 ft

END OF BORING 42 ft
ELEVATION 743.5 ft




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYDRATED GRANULAR/CHIPS CONCRETE
3. HYDRATED BENTONITE
GRANULAR/CHIPS, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 25.3 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS/PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP3

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/29/93
Contractor	E & F
Coordinates	2116428.7N, 1050918.9E




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYDRATED CHIPS
CONCRETE
3. HYDRATED BENTONITE
CHIPS, FINE SILICA SAND
4. PVC PIPE
DIAMETER 2 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 2 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 14.5 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS/PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP4

Project HOD LANDFILL
 Location ANTIOCH, ILLINOIS
 Job No. 10010201
 Date Constructed 5/4/93
 Contractor E & F
 Coordinates 2116110.6N, 1051338.6E



1. LOCKING STEEL PROTECTIVE CASING
 DIAMETER 8 IN
 LENGTH 7 FT
2. SURFACE SEAL
 BENTONITE HYD. CHIPS/GRANULAR
 CONCRETE _____
3. HYDRATED BENTONITE
CHIPS/GRANULAR, FINE SILICA SAND
4. PVC PIPE
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
 SLOT SIZE 0.020 IN
 LENGTH 29.1 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS, PEA GRAVEL
8. BOREHOLE
 DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP

SJC:rgDAP


J:\10010201-LP4.XLS



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP5

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/21/93
Contractor	E & F
Coordinates	2116230N, 1051719.6E




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. CHIPS/GRANULAR
CONCRETE _____
3. HYDRATED BENTONITE
CHIPS/GRANULAR
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 39.5 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS, PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP6

Project	<u>HOD LANDFILL</u>
Location	<u>ANTIOCH, ILLINOIS</u>
Job No.	<u>10010201</u>
Date Constructed	<u>4/16/93</u>
Contractor	<u>E & F</u>
Coordinates	<u>2115990.2N, 1051732.1E</u>




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. CHIPS/GRANULAR
CONCRETE _____
3. HYDRATED BENTONITE
CHIPS/GRANULAR, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 26.8 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
WASHED PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP7

Project	<u>HOD LANDFILL</u>
Location	<u>ANTIOCH, LANDFILL</u>
Job No.	<u>10010201</u>
Date Constructed	<u>4/29/93</u>
Contractor	<u>E & F</u>
Coordinates	<u>2116197.8N, 1052105.4E</u>




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. GRANULAR/CHIPS
CONCRETE _____
3. HYDRATED BENTONITE
GRANULAR/CHIPS, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 51.5 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS/PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP8

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/27/93
Contractor	E & F
Coordinates	2116218.6N, 1052519.4E




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. CHIPS/GRANULAR
CONCRETE
3. HYDRATED BENTONITE
CHIPS/GRANULAR, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 60 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS, PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP9

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/23/93
Contractor	E & F
Coordinates	2116220.4N, 1052769.9E



1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD CHIPS/GRANULAR
CONCRETE
3. HYDRATED BENTONITE
CHIPS/GRANULAR, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 57.3 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS THEN PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP

SIC:rs-DAP


J:\10010201\LP9.XLS



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP10

Project HOD LANDFILL
 Location ANTIOCH, ILLINOIS
 Job No. 10010201
 Date Constructed 4/30/93
 Contractor E & F
 Coordinates 2115810.4N, 1050919.8E



1. LOCKING STEEL PROTECTIVE CASING
 DIAMETER 8 IN
 LENGTH 7 FT
2. SURFACE SEAL
 BENTONITE HYD. GRANULAR/CHIPS
 CONCRETE
3. HYDRATED BENTONITE
GRANULAR/CHIPS, AND FINE SILICA SAND
4. PVC PIPE
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
 SLOT SIZE 0.020 IN
 LENGTH 13.5 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
BENTONITE CHIPS
8. BOREHOLE
 DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP

SCALE: 1" = 10'


DATE: 10/1/93



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP11

Project	<u>HOD LANDFILL</u>
Location	<u>ANTIOCH, ILLINOIS</u>
Job No.	<u>10010201</u>
Date Constructed	<u>4/12/93</u>
Contractor	<u>E & F</u>
Coordinates	<u>2115807.1N, 1051321.8E</u>




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. CHIPS/GRANULAR
CONCRETE _____
3. HYDRATED BENTONITE
CHIPS/GRANULAR & FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 21.7 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
WASHED PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP12

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/8/93
Contractor	E & F
Coordinates	2115515.5N, 1051138.4E




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. GRANULAR/CHIPS
CONCRETE _____
3. HYDRATED BENTONITE
GRANULAR/CHIPS AND FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 12.5 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
WASHED PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP13

Project	HOD LANDFILL
Location	ANTIOCH, ILLINOIS
Job No.	10010201
Date Constructed	4/13/93
Contractor	E & F
Coordinates	2115448.4N, 1050899.8E




1. LOCKING STEEL PROTECTIVE CASING
DIAMETER 8 IN
LENGTH 7 FT
2. SURFACE SEAL
BENTONITE HYD. CHIPS/GRANULAR
CONCRETE _____
3. HYDRATED BENTONITE
GRANULAR/CHIPS, FINE SILICA SAND
4. PVC PIPE
DIAMETER 6 IN ID
SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
DIAMETER 6 IN ID
SCHEDULE 80 PVC
SLOT SIZE 0.020 IN
LENGTH 7.17 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
WASHED PEA GRAVEL
8. BOREHOLE
DIAMETER 14 IN
9. PROBE TOP Vented Slip Cap



LEACHATE PIEZOMETER DETAIL

LEACHATE PIEZOMETER NO. LP14

Project HOD LANDFILL
 Location ANTIOCH, ILLINOIS
 Job No. 10010201
 Date Constructed 4/14/93
 Contractor E & F
 Coordinates 2115474.5N, 1051389.5E



1. LOCKING STEEL PROTECTIVE CASING
 DIAMETER 8 IN
 LENGTH 7 FT
2. SURFACE SEAL
 BENTONITE HYD. CHIPS/GRANULAR
 CONCRETE
3. HYDRATED BENTONITE
CHIPS/GRANULAR, FINE SILICA SAND
4. PVC PIPE
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
5. SLOTTED PVC SCREEN
 DIAMETER 6 IN ID
 SCHEDULE 80 PVC
 SLOT SIZE 0.020 IN
 LENGTH 12.3 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
WASHED PEA GRAVEL
8. BOREHOLE
 DIAMETER 14 IN
9. PROBE TOP VENTED SLIP CAP

C

PERIMETER GAS PROBE
BORING LOGS AND
PROBE CONSTRUCTION DETAILS

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. GP3
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9, T 46 N, R 10 E/W		SHEET 1 OF 1
NORTHING 2116615.5	EASTING 1052220.9	DRILLING START TIME FINISH TIME
DATUM	ELEVATION 770.8	DATE DATE
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED SURFACE	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS					
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS	
768.3	63		1	Brown TOPSOIL, Roots Present, Clayey Little to Some Sand to 1 Foot over Brown Sandy Clay to Silty Clay. Little to Some, Fine to Medium Sand to 2 Feet over 6" Moist Sand Layer	SB								1->4.5
5	100		2	Hard Brown and Gray Streaked Silty CLAY (CL), Little Fine to Coarse Sand, Grades to Little Fine Gravel, Limonite Patches and Gray Streaks Hard Brown Silty CLAY (CL) Trace to Little Fine to Coarse Sand, Trace Fine Gravel, Gray Streaks Present	SB								>4.5
10	97		3	PID None Detected	SB								>4.5-3.5
758.8	100		4	Very Stiff to Hard Gray Silty CLAY (CL), Trace to Little Fine to Coarse Sand, Trace Gravel	SB								2.75->4.5
15				PID None Detected									
20				End of Boring at 20 Feet Gas Probe Set at 19.85 Feet									
25													
30													
35													

LOGGED BY SJC	DRILLING CONTR E&F
DATE 9/22/93	CHK'D BY DAP
	CHAS. MARKGRAF
	ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois		DRILLING METHOD: 4 1/4" IDHSA	BORING NO. GP4	
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9, T 46 N, R 10 E/W		SAMPLING METHOD: 5 FT CME SAMPLING TUBE 2" SPLIT SPOON	SHEET 1 OF 1	
NORTHING	EASTING	WATER LEVEL	DRILLING	START TIME
DATUM	ELEVATION	TIME	DATE	DATE
DRILL RIG CME 750 ATV	SURFACE CONDITIONS		4/15/93	4/15/93
ANGLE Vertical	BEARING -----			

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS

5	-	96	█	1	FILL: Organic Topsoil. Roots Present Brown Silty Clay Cap Material Brown Silty Clay Grades to Little Brown Clay	SB						0.54
5	-	75	█	2	Refuse. Cloth Material at 4 Feet Plastic Material at 5 Feet	SB						-
10					End of Boring at 6 Feet Boring Backfilled with Bentonite Chips							
15												
20												
25												
30												
35												

LOGGED BY <u>SJC</u>	DRILLING CONTR <u>CM</u>
DATE <u>9/22/93</u>	CHK'D BY <u>DAP</u>
	<u>CHAS. MARKGRAF</u>

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. GP4A
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9 , T 46 N, R 10 E/W		SHEET 1 OF 1
NORTHING 2116248.1 EASTING 1053013.8		DRILLING START TIME FINISH TIME
DATUM ELEVATION 776.4		DATE DATE
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED	4/15/93 4/15/93
ANGLE Vertical BEARING -----	WATER LEVEL	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS
775.4	-	67	1	10" Topsoil Over 4" Brown Sandy Clay, 1/2" Sand Lense at 14" Very Stiff to Hard Gray CLAY (CH)	SB						25 - >4.5	
773.4	-	100	2	Very Stiff Brown CLAY (CH), Trace Fine to Coarse Sand, Trace Silt Very Stiff Brown Silty CLAY (CL), Little Fine to Coarse Sand, Trace to Little Fine Gravel, Trace Coarse Gravel	SB						>4.5	
5 771.4	-	97	3	3" Sandy Gravelly Clay Layer at 8 Feet, Grades to Very Stiff Brown and Gray Silty CLAY (CL) Little Fine to Coarse Sand, Trace to Little Gravel Very Stiff Gray Lean CLAY (CL), Trace to Some Silt, Little Fine to Coarse Sand, Trace to Little Fine Gravel, Trace Coarse Gravel 1" Sand Lense at 11 Feet	SB						3-4	
15 761.9	-	95	4	3" Silt Layer at 14 Feet Very Stiff Gray Lean CLAY (CL) Trace to Some Silt, Little Fine to Coarse Sand and Fine Gravel, Shale Fragments Present	SB						2.5-3.5	
20	-	95	5	Silt Lenses Present 1" Silt Layer at 21 Feet	SB						2.5-3.5	
25 752.8	-	67	6	1" Sand and Gravel Layer at 23.5 Feet Very Stiff Gray Sandy Gravelly CLAY (CL) 2" Sand and Gravel Layer at 25.5 Feet	SB						-	
27 749.4	End of Boring at 27 Feet Gas Probe Set at 26 Feet											
30												
35												

LOGGED BY SJC	DRILLING CONTR E&F
DATE 9/17/93	CHK'D BY DAP
	CHAS. MARKGRAF
Template ID: 101	ID: WMI

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch, Illinois**

DRILLING METHOD: **4 1/4" IDHSA**

BORING NO. **GP5**

SHEET

SAMPLING METHOD: **5 FT CME SAMPLING TUBE**

1 OF **1**

DRILLING

START TIME

FINISH TIME

BORING LOCATION:

SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W

NORTHING

EASTING

DATUM

ELEVATION

WATER LEVEL

TIME

DATE

DATE

DATE

CASING DEPTH

4/16/93 4/16/93

DRILL RIG **CME 750 ATV**

SURFACE CONDITIONS **GRASS COVERED LANDFILL CAP**

ANGLE **Vertical**

BEARING **-----**

SAMPLE HAMMER TORQUE

FT-LBS

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
5	92			1 FILL: Brown Silt and Wet Organic Clay Topsoil Over Brown and Gray Silty Clay, Little to Some Fine to Coarse Sand, Trace Coarse Gravel Sandy Lenses from 2-4 Feet	SB									->4.5
	83			2 FILL: Gray Clay	SB									-
10				Refuse Material at 9 Feet End of Boring at 9 Feet Boring Backfilled with Bentonite Chips										
15														
20														
25														
30														
35														

LOGGED BY **SJC**

DRILLING CONTR **E&F**

DATE **9/17/93**

CHK'D BY **DAP**

CHAS. MARKGRAF

ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. GP5A
SAMPLING METHOD: 5 FT CME SAMPLING TUBE		SHEET 1 OF 1
DRILLING		
WATER LEVEL		START TIME FINISH TIME
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W		DATE DATE
NORTHING 2115682.3	EASTING 1051583.3	DATE DATE
DATUM	ELEVATION 768.4	CASING DEPTH 4/22/93 4/22/93
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED SURFACE	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
	-	75	[Symbol]	1 FILL: Brown Wet Topsoil with Grass Roots with Little to Some Fine to Coarse Sand, Trace Gravel	SB									1-2
	-	90	[Symbol]	2 FILL: Grades to Hard Silty Clay with Little Fine to Coarse Sand, Trace Gravel, Brown Sandy Clay, Brush Fibers Observed in Brown Clay FILL: Gray and Black Clay to 6 Feet	SB									75-2
5				Fibrous PEAT (PT)										
	-	52	[Symbol]	3 Soft Gray CLAY (CH), Little Fine to Coarse Sand	SB									25-1
10				Stiff Brown and Gray Mottled Silty CLAY (CL)										
	-	92	[Symbol]	4 Stiff to Very Stiff Gray Silty CLAY (CL) Grades to Gray Clayey SILT to Silty CLAY (CL/ML), Little to Some Fine to Coarse Sand, Trace Fine Gravel to 13 Feet Grades to Gray Silty CLAY (CL), Little Fine to Coarse Sand, Trace Fine Gravel	SB									1.5- 2.5
15				Very Stiff Yellowish Brown and Gray Mottled Silty CLAY (CL) Grading to Clayey SILT, Silty CLAY (CL/ML), Trace to Little Fine to Coarse Sand, Trace Fine to Coarse Wet Gravel 3" Gray Silty Layer at 16.5 Feet	SB									1.5- 2.75
	-	98	[Symbol]	5 Stiff to Very Stiff Gray Clayey SILT, Silty CLAY (CL/ML) Grades to Gray Silty CLAY (CL)	SB									
20				End of Boring at 22 Feet Gas Probe Installed at 16.1 Feet										
25														
30														
35														

LOGGED BY SJC

DRILLING CONTR E&F

DATE 9/17/93

CHK'D BY DAP

CHAS. MARKGRAF


ID: WM1



GAS MONITORING PROBE

GAS PROBE NO. GP3

Project HOD Landfill
 Location Antioch, Illinois
 Job No. 10010201
 Date Constructed 4/21/93
 Contractor E & F Drilling
 Coordinates 2116615.5N, 1052220.9E



1. LOCKING ALUMINUM PROTECTIVE CASING LENGTH 5 FT
2. SURFACE SEAL BENTONITE HYDRATED CONCRETE _____
3. HYDRATED BENTONITE GRANULAR TO SURFACE
4. PVC PIPE DIAMETER 2 IN ID SCHEDULE 40 PVC
5. SLOTTED PVC SCREEN DIAMETER 2 IN ID SCHEDULE 40 PVC SLOT SIZE 0.020 IN. LENGTH 14.65'
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM N/A
8. BOREHOLE DIAMETER 8.5 IN.
9. PROBE TOP VENTED PUSH CAP

SI-CMS3/AP


J-10010201-GP3.XLS



GAS MONITORING PROBE

GAS PROBE NO. GP4A

Project	<u>HOD LANDFILL</u>
Location	<u>ANTIOCH, ILLINOIS</u>
Job No.	<u>10010201</u>
Date Constructed	<u>4/15/93</u>
Contractor	<u>E & F</u>
Coordinates	<u>2116248.1N 1053013.7E</u>




1. LOCKING STEEL PROTECTIVE CASING
LENGTH 5 FT
2. SURFACE SEAL
BENTONITE HYDRATED
CONCRETE _____
3. HYDRATED BENTONITE
CHIPS AND GRANULAR TO SURFACE
4. PVC PIPE
DIAMETER 2 IN ID
SCHEDULE 40 PVC
5. SLOTTED PVC SCREEN
DIAMETER 2 IN ID
SCHEDULE 40 PVC
SLOT SIZE 0.020 IN
LENGTH 20.7 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM
PEA GRAVEL
8. BOREHOLE
DIAMETER 8.5 IN
9. PROBE TOP VENTED PUSH CAP



GAS MONITORING PROBE

GAS PROBE NO. GP5A

Project HOD LANDFILL
 Location ANTIOCH, ILLINOIS
 Job No. 10010201
 Date Constructed 4/22/93
 Contractor E & F
 Coordinates 2115682.3N, 1051583.3E



1. LOCKING STEEL PROTECTIVE CASING LENGTH 5 FT
2. SURFACE SEAL BENTONITE HYDRATED GRANULAR CONCRETE
3. HYDRATED BENTONITE GRANULAR
4. PVC PIPE DIAMETER 2 IN ID SCHEDULE 40 PVC
5. SLOTTED PVC SCREEN DIAMETER 2 IN ID SCHEDULE 40 PVC SLOT SIZE 0.020 IN LENGTH 10.09 FT
6. PEA GRAVEL WASHED
7. BORING BACKFILL TO SCREEN BOTTOM BENTONITE TO 17 FT THEN PEA GRAVEL
8. BOREHOLE DIAMETER 8.5 IN
9. PROBE TOP VENTED SLIP CAP

SIC 98/04AP

J:\001-24-GP5A.XLS

D

GEOPHYSICAL LOGS



Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-Fitemp-Neut

COMPANY: WARZYN
 WELL: LP01
 FIELD: HOD Antioch, IL

LOCATION:
 2116410.7
 1050909.7

OTHER LOGS:

PERM. DATUM: GROUND LEVEL
 ELEVATION: 775.6
 LOG MEASURED FROM: GROUND LEVEL

DATE	14 May 93			
RUN NUMBER	ONE			
DRILLER				
TYPE OF CASING	6" PVC			
SCREEN INTERVAL				
LOGGER				
DEPTH	20.6'			
CASING DEPTH				
BOT LOG INTERVAL				
TOP LOG INTERVAL	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate			
FLUID LEVEL				
SAMPLE SOURCE				
FLUID LVL / CIRC				
TIME SINCE CIRC STOP				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chillsom			


RUN #	PROBE TYPE / SN	MODULE TYPE / SN	LOGGING SPEED	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =	GAMMA	FLTEMP	B DENSITY	NEUTRON
	COM-G11/4	CS01 F22	10 ft./minute		0.2	00-G11/4	00-T11/4	00-BD 21/B	COM-N11/4
						CS01 F22	CS01 F00	CS22 F22	CS10 F22

COMMENT:

FLUID TEMP

LP01

COMMENTS:					



WLI

Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Den-Fitemp-Neut

COMPANY: WARZYN
WELL: LPO2
FIELD: HOD Antioch, IL

LOCATION:
2116428.7
1051349.0

OTHER LOGS:


PERM. DATUM: GROUND LEVEL
ELEVATION: 785.5
LOG MEASURED FROM: GROUND LEVEL

DATE:	14 May 93			
RUN NUMBER:	ONE			
DRILLER:				
TYPE OF CASING:	6" PVC			
SCREEN INTERVAL:				
LOGGER:				
DEPTH:	35.0'			
CASING DEPTH:				
BOT LOG INTERVAL:				
TOP LOG INTERVAL:	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE:	Leachate			
FLUID LEVEL:				
SAMPLE SOURCE:				
FLUID LV./CIRC:				
TIME SINCE CIRC.STOP:				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chilson			

RUN /	NEUTRON	B. DENSITY	FLTEMP	GAMMA
PROBE TYPE / SIN	COM-N11/4	GO-BD 21/8	GO-T11/4	COM-G11/4
MODULE TYPE / SIN	CSI0 F22	CS22 F22	CS01 F00	CS01 F22
AFTER SURVEY DEPTH ERROR	10 ft./minute	10 ft./minute	-7 ft./minute	10 ft./minute
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				



COMMENTS:				





Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-FItemp-Neut


COMPANY: WARZYN
 WELL: LP03
 FIELD: HOD Antioch, IL
 LOCATION:
 21160827
 10509183

OTHER LOGS:


PERM. DATUM: GROUND LEVEL
 ELEVATION: 778.1'
 LOG MEASURED FROM: GROUND LEVEL

DRILLER:	14 May 93		
RUN NUMBER:	ONE		
TYPE OF CASING:	6" Pac		
SCREEN INTERVAL:			
LOGGER:			
DEPTH	25.4'		
CASING DEPTH			
BOT LOG INTERVAL			
TOP LOG INTERVAL	0.00	0.00	
TYPE FLUID IN HOLE	Levexite	0.00	0.00
FLUID LEVEL			
SAMPLE SOURCE			
FLUID LVL / DIBC			
TIME SINCE CIRC STOP:			
RECORDED BY:	Duke & Wooddell		
OBSERVER:	Mr. Steve Chilson		

RUN #	GAMMA	FLTEMP	B. DENSITY	NEUTRON
PROBE TYPE / SN	COM-G11/4	GO-T11/4	GO-BD 21/8	COM-N11/4
MODULE TYPE / SN	CS01 F22	CS01 F00	CS22 F22	CS10 F22
LOGGING SPEED	10 ft./minute	-7 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				



SAMPLE INTERVAL =			
COMMENTS:			





Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-FItemp-Neut

COMPANY: WARZYN
 WELL: LP04
 FIELD: HOD Antioch, IL

LOCATION:
 21161106
 10513386

PERM. DATUM: GROUND LEVEL
 ELEVATION: 788.9
 LOG MEASURED FROM: GROUND LEVEL


DATE: 20 May 93
 RUN BY: ONE

DRILLER:
 TYPE OF CASING: 8" PVC


SCREEN INTERVAL:

LOGGER:	
DEPTH	39.0
CASING DEPTH	
TOP LOG INTERVAL	0.00
TOP LOG INTERVAL	0.00
TYPE FLUID IN HOLE	Leachate
FLUID LEVEL	
SAMPLE SOURCE	
FLUID T.V./CIRC	
TIME SINCE CIRC STOP	
RECORDED BY	Drae & Woodell
OBSERVER	Mr. Steve Chilson

RUN #	GAMMA	FLTEMP	B DENSITY	NEUTRON
PROBE TYPE / SN	COM-G 1 1/4	GO-T 1 1/4	GO-BD 2 1/8	COM-N 1 1/4
MODULE TYPE / SN	CS01 F22	CS01 F00	CS22 F22	CS10 F22
LOGGING SPEED	10 ft./minute	-7 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				



COMMENTS:				



WLI

Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Den-Ftemp-Neut

COMPANY: WARZYN
WELL: LP06
FIELD: HOD Antioch, IL
LOCATION:
2115990.2
1051732.1


OTHER LOGS:

PERM. DATUM: GROUND LEVEL
ELEVATION: 794.6'
LOG MEASURED FROM: GROUND LEVEL


DATE	19 May 93			
RUN NUMBER	ONE			
DRILLER:				
TYPE OF CASING	6" PVC			
SCREEN INTERVAL				
LOGGER:				
DEPTH	35.6'			
CASING DEPTH				
BOT LOG INTERVAL				
TOP LOG INTERVAL	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate			
FLUID LEVEL				
SAMPLE SOURCE				
FLUID LVL./CIRC.				
TIME SINCE CIRC.STOP.				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chilsron			

RUN #					
PROBE TYPE / SIN	COM-G11/4	COM-N11/4			
MODULE TYPE / SIN	CS01 F22	CS22 F22			
LOGGING SPEED	10 ft./minute	10 ft./minute			
AFTER SURVEY DEPTH ERROR	-7 ft./minute	10 ft./minute			
SAMPLE INTERVAL =	0.2	0.2			


COMMENTS:



COMMENTS:					



AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				



		Wooddell Logging Inc.	
Mattoon, Illinois 217 234-8525			
Gamma-Den-Fltemp-Neut			
COMPANY: WARZYN			
WELL: LP12			
FIELD: HOD Antioch, IL			
LOCATION: 211551.5.5 1051138.4		OTHER LOGS:	
PERM. DATUM: GROUND LEVEL			
ELEVATION: 782.6'			
LOG MEASURED FROM: GROUND LEVEL			
DATE	20 MAY 93		
RUN NUMBER	ONE		
DRILLER:			
TYPE OF CASING	6" PVC		
SCREEN INTERVAL			
LOGGER:			
DEPTH	22.8'		
CASING DEPTH			
BOT LOG INTERVAL			
TOP LOG INTERVAL	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate		
FLUID LEVEL			
SAMPLE SOURCE			
FLUID LW/CIRC			
TIME SINCE CIRC STOP			
RECORDED BY:	Drake & Wooddell		
OBSERVER:	Mr. Steve Chilton		


PROBE TYPE / SN	CON-G11/4	GAMMA	GO-T11/4	FLTEMP	GO-BO21/8	B DENSITY	COM-N11/4	NEUTRON
MODULE TYPE / SN	CS01 F22		CS01 F00		CS22 F22			
LOGGING SPEED	10 ft./minute		-7 ft./minute		10 ft./minute			
AFTER SURVEY DEPTH ERROR								
SAMPLE INTERVAL =	0.2				0.2			0.2
COMMENTS:								

LP12

FLUID TEMP
DEG F 70 ←

50

LOGGING SPEED	10 ft./minute	- / ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				





Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Den-FItemp-Neut

COMPANY: WARZYN

WELL: LP13

FIELD: HOD Antioch, IL

LOCATION:

2115448.4
1050899.8

OTHER LOGS:


PERM. DATUM: GROUND LEVEL
ELEVATION: 779'
LOG MEASURED FROM: GROUND LEVEL

DATE:	20 May 93			
RUN NUMBER:	ONE			
DRILLER:				
TYPE OF CASING:	6" PVC			
SCREEN INTERVAL:				
LOGGER:				
DEPTH:	16.6'			
CASING DEPTH:				
BOT LOG INTERVAL:				
TOP LOG INTERVAL:	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE:	Leachate			
FLUID LEVEL:				
SAMPLE SOURCE:				
FLUID LV./CIRC:				
TIME SINCE CIRC. STOP:				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chillson			


RUN #	PROBE TYPE / SN	MODULE TYPE / SN	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =	GAMMA	FI TEMP	B DENSITY	NEUTRON	
	COM-611/4	CS01 F22	10 ft./minute	0.2					
	COM-T11/4	CS01 F00	-7 ft./minute	0.2					
	CO-BD21/B	CS22 F22	10 ft./minute	0.2					
	COM-N11/4	CS10 F22	10 ft./minute	0.2					
					COMMENTS:				

LP13

AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	2	0.2	0.2
COMMENTS:				



COMMENTS:				





Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-Temp-Neut

COMPANY: WARZYN
 WELL: LP05
 FIELD: HOD Antioch, IL


LOCATION:
 2116230.0
 1051719.6
 OTHER LOGS:

PERM. DATUM: GROUND LEVEL
 ELEVATION: 796.6'
 LOG MEASURED FROM: GROUND LEVEL

DATE	19 May 93		
RUN NUMBER	ONE		
DRILLER:			
TYPE OF CASING	6" PVC		
SCREEN INTERVAL			
LOGGER:			
DEPTH	50.0'		
CASING DEPTH			
BOT LOG INTERVAL			
TOP LOG INTERVAL	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate		
FLUID LEVEL			
SAMPLE SOURCE			
FLUID LVL./CIRC.			
TIME SINCE CIRC.STOP.			
RECORDED BY	Drake & Wooddel		
OBSERVER	Mr. Steve Chilson		


RUN #					
PROBE TYPE / SN	COM-G11/4	COM-N11/4	NEUTRON	CS10F22	10 ft./minute
MODULE TYPE / SN	CS01 F22	CS22 F22	B. DENSITY	CS22 F22	10 ft./minute
LOGGING SPEED	10 ft./minute		FLTEMP	CS01 F00	-7 ft./minute
AFTER SURVEY DEPTH ERROR					
SAMPLE INTERVAL =	0.2				0.2

COMMENTS:



Engineering Inc.	
Neut	
h. JL	
OTHER LOGS:	
VEL	
EL	
0.00	0.00


RUN / PROBE TYPE / SN	GAMMA	FLUTEMP	B. DENSITY	NEUTRON
GO-111/4	COM-G11/4	GO-111/4	GO-B021/8	COM-N11/4
CS01 F22	CS01 F22	CS01 F00	CS22 F22	CS10 F22
10 ft./minute	10 ft./minute	-7 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR	0.2	0.2	0.2	0.2
SAMPLE INTERVAL =				



COMMENTS:

COMMENTS:

LP05



GAMMA CPS 0 45
FLUID TEMP DEG F 50 70
BULK DENSITY CPS 350 50 * 0
NEUTRON CPS 250
LP05



Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-Fltemp-Neut

COMPANY: WARZYN

WELL: LP07

FIELD: HOD Antioch, IL

LOCATION:
 2116197.8
 1052105.4

OTHER LOGS:

PERM. DATUM: GROUND LEVEL

ELEVATION: 794.7'

LOG MEASURED FROM: GROUND LEVEL

DATE:	19 May 93			
RUN NUMBER:	ONE			
DRILLER:				
TYPE OF CASING:	6" PVC			
SCREEN INTERVAL:				
LOGGER:				
DEPTH:	58.4'			
CASING DEPTH:				
BOT LOG INTERVAL:				
TOP LOG INTERVAL:	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE:	Leachate			
FLUID LEVEL:				
SAMPLE SOURCE:				
FLUID LV./CIRC.				
TIME SINCE CIRC.STOP.				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chilton			

RUN /	PROBE TYPE / SN	MODULE TYPE / SN	LOGGING SPEED	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =	GAMMA	FLTEMP	B DENSITY	NEUTRON
	GM-T11/4	GM-T11/4	CS01 F22	-7 ft/minute	0.2	GO-111/4	GO-111/4	GO-1021/8	COM-NI 1/4
	CS01 F22	CS01 F22	10 ft/minute					CS22 F22	CS10 F22
								10 ft/minute	10 ft/minute
									0.2

COMMENTS:


LP07


FLUID TEMP
DEG F

70

NEUTRON

RUN #	GAMMA	FL TEMP	B. DENSITY	NEUTRON
PROBE TYPE / SN	COM-G11/4	GO-T11/4	GO-BD 21/8	COM-N11/4
MODULE TYPE / SN	CS01 F22	CS01 F00	CS22 F22	CS10 F22
LOGGING SPEED	10 ft/minute	-7 ft/minute	10 ft/minute	10 ft/minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				







Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Den-FItemp-Neut

COMPANY: WARZYN

WELL: LPO8

FIELD: HOD Antioch, IL

LOCATION:

2116218.6
1052519.4

OTHER LOGS:

PERM. DATUM: GROUND LEVEL
ELEVATION: 793.5'
LOG MEASURED FROM: GROUND LEVEL


DATE	19 May 93			
RUN NUMBER	ONE			
DRILLER:				
TYPE OF CASING	6" PVC			
SCREEN INTERVAL:				
LOGGER:				
DEPTH	69.0'			
CASING DEPTH				
BOT LOG INTERVAL				
TOP LOG INTERVAL	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate			
FLUID LEVEL				
SAMPLE SOURCE				
FLUID LV./CIRC				
TIME SINCE CIRC.STOP.				
RECORDED BY:	Drake & Wooddell			
OBSERVER	Mr. Steve Chilton			


RUN /									
PROBE TYPE / SN	COM-G11/A	GAMMA	FLTEMP	B DENSITY	NEUTRON				
MODULE TYPE / SN	CS01 F22	COM-G11/A	GO-T11/A	GO-BD 21/B	COM-N11/A				
LOGGING SPEED	10 ft./minute	CS01 F22	CS01 F00	CS22 F22	CS10 F22				
AFTER SURVEY DEPTH ERROR		10 ft./minute	-7 ft./minute	10 ft./minute	10 ft./minute				
SAMPLE INTERVAL =	0.2		0.2	0.2	0.2				
COMMENTS:									

FLUID TEMP LPO8

RUN #	GAMMA	FL TEMP	B DENSITY	NEUTRON
PROBE TYPE / S/N	COM-G 1 1/4	GO-T 1 1/4	GO-BD 2 1/8	COM-N 1 1/4
MODULE TYPE / S/N	CS01 F22	CS01 F00	CS22 F22	CS10 F22
LOGGING SPEED	10 ft/minute	-7 ft/minute	10 ft/minute	10 ft/minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2

COMMENTS:






Wooddell Logging Inc.
 Mattoon, Illinois
 217 234-8525

Gamma-Den-Fi temp-Neut

COMPANY: WARZYN

WELL: LP09

FIELD: HOD Antioch, IL

LOCATION:

2116220.4

1052769.9

OTHER LOGS:

PERM. DATUM: GROUND LEVEL


ELEVATION: 785.8'

LOG MEASURED FROM: GROUND LEVEL


DATE:	19 May 93			
RUN NUMBER:	ONE			
DRILLER:				
TYPE OF CASING	6" PVC			
SCREEN INTERVAL				
LOGGER:				
DEPTH	64.6'			
CASING DEPTH				
BOT LOG INTERVAL				
TOP LOG INTERVAL	0.00	0.00	0.00	0.00
TYPE FLUID IN HOLE	Leachate			
FLUID LEVEL				
SAMPLE SOURCE				
FLUID LV./CIRC.				
TIME SINCE CIRC.STOP.				
RECORDED BY:	Drake & Wooddell			
OBSERVER:	Mr. Steve Chillson			


RUN /	PROBE TYPE / SN	MODULE TYPE / SN	LOGGING SPEED	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =	DEPTH	GAMMA	FLTEMP	B DENSITY	NEUTRON
	COM-G11/4	CS01 F22	10 ft./minute		0.2					
	GO-T11/4	CS01 F00	-7 ft./minute		0.2					
	GO-BD 21/8	CS22 F22	10 ft./minute		0.2					
	COM-N11/4	CS10 F22	10 ft./minute		0.2					

COMMENTS:



PROBE TYPE / S/N	COM-G 1 1/4	GO-T 1 1/4	GO-BD 2 1/8	COM-N 1 1/4
MODULE TYPE / S/N	CS01 F22	CS01 F00	CS22 F22	CS10 F22
LOGGING SPEED	10 ft./minute	-7 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2	0.2	0.2	0.2
COMMENTS:				





1 D00



Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Density-Neutron

COMPANY: WARZYN
WELL: W2D
FIELD: HOD Antioch, IL

LOCATION:
2116648.2
1052499.9

OTHER LOGS:


PERM. DATUM: GROUND LEVEL
ELEVATION: 770.7'
LOG MEASURED FROM: GROUND LEVEL


DATE:	04 June 93
RUN NUMBER:	ONE
DRILLER:	
BIT DIA TO	8 1/2" TO 88.33
SCREEN INTERVAL	83.3 TO 88.3
TYPE OF CASING	PVC
SIZE OF CASING	
LOGGER:	
DEPTH	87.4'
CASING DEPTH	
BOT LOG INTERVAL	
TOP LOG INTERVAL	
TYPE FLUID IN HOLE	Water
FLUID LEVEL	
SAMPLE SOURCE	
FLUID LVL./CIRC.	
TIME SINCE CIRC.STOP.	
RECORDED BY:	Drake & Wooddell
OBSERVER:	Mr. Steve Chilson

RUN /	PROBE TYPE / SN	MODULE TYPE / SN	LOGGING SPEED	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =
	COM-G11/4	CS01 F22	10 ft./minute		0.2
	B. DENSITY	GO-80 21/8	CS22 F22	10 ft./minute	0.2
	NEUTRON	COM-N1 1/4	CS10 F22	10 ft./minute	0.2

COMMENTS:

RUN #	GAMMA	B. DENSITY	NEUTRON
PROBE TYPE / S.N.	COM-G 1 1/4	GO-BD 2 1/8	COM-N 1 1/4
MODULE TYPE / S.N.	CS01 F22	CS22 F22	CSI 0 F22
LOGGING SPEED	10 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR			
SAMPLE INTERVAL =	0.2	0.2	0.2
COMMENTS:			





WLI

Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma

COMPANY: WARZYN

WELL: W3D

FIELD: HOD Antioch, IL


LOCATION:
2115187.6
1051022.7


OTHER LOGS:

PERM. DATUM: GROUND LEVEL
ELEVATION: 763.7'
LOG MEASURED FROM: GROUND LEVEL


DATE:	03 June 93		
RUN NUMBER:	ONE		
DRILLER:			
BIT DIA. TO	8 1/2" TO 78		
SCREEN INTERVAL	73.3 TO 77.6'		
TYPE OF CASING	PVC		
SIZE OF CASING			
LOGGER:			
DEPTH	75.4'		
CASING DEPTH			
BOT LOG INTERVAL			
TOP LOG INTERVAL			
TYPE FLUID IN HOLE	Water		
FLUID LEVEL			
SAMPLE SOURCE			
FLUID LV./CIRC.			
TIME SINCE CIRC.STOP.			
RECORDED BY:	Drake & Wooddell		
OBSERVER:	Mr. Steve Chillson		


RUN #				
PROBE TYPE / SN	COM-G11/A			
MODULE TYPE / SN	GS01 F22			
LOGGING SPEED	10 ft./minute			
AFTER SURVEY DEPTH ERROR				
SAMPLE INTERVAL =	0.2			
COMMENTS:				





COMMENTS:				





WLI

Wooddell Logging Inc.

Mattoon, Illinois
217 234-8925

Gamma-Density-Neutron

COMPANY: WARZYN

WELL: US4D

FIELD: HOD Antioch, IL

LOCATION:
2115377.8
1050754.4


OTHER LOGS:


PERM. DATUM: GROUND LEVEL
ELEVATION: 770.5'
LOG MEASURED FROM: GROUND LEVEL

DATE:	04 June 93				
RUN NUMBER:	ONE				
DRILLER:					
BIT DIA. TO					
SCREEN INTERVAL					
TYPE OF CASING					
SIZE OF CASING					
LOGGER:					
DEPTH	102.4'				
CASING DEPTH					
BOT LOG INTERVAL					
TOP LOG INTERVAL					
TYPE FLUID IN HOLE	Water				
FLUID LEVEL					
SAMPLE SOURCE					
FLUID LVL /CIRC.					
TIME SINCE CIRC.STOP.					
RECORDED BY:	Drake & Wooddell				
OBSERVER	Mr. Steve Chillson				

RUN /	GAMA	B DENSITY	NEUTRON
PROBE TYPE / SN	COM-G11/A	CO-BD 21/B	COM-M11/A
MODULE TYPE / SN	CS01 F22	CS02 F22	CS10 F22
LOGGING SPEED	10 ft./minute	10 ft./minute	10 ft./minute
AF TER SURVEY DEPTH ERROR			
SAMPLE INTERVAL =	0.2	0.2	0.2

COMMENTS:







Wooddell Logging Inc.

Mattoon, Illinois
217 234-8525

Gamma-Density-Neutron

COMPANY: WARZYN

WELL: US6D

FIELD: HOD Antioch, IL

LOCATION:
2115387.7
1051523.3


OTHER LOGS:

PERM. DATUM: GROUND LEVEL
ELEVATION: 767.1'
LOG MEASURED FROM: GROUND LEVEL

DATE:	04 June 93			
RUN NUMBER:	ONE			
DRILLER:				
BIT DIA. TO	8 1/2" TO 8 3/4"			
SCREEN INTERVAL	77.9 TO 8317			
TYPE OF CASING	STAINLESS			
SIZE OF CASING				
LOGGER:				
DEPTH	81.0'			
CASING DEPTH				
BOT LOG INTERVAL				
TOP LOG INTERVAL				
TYPE FLUID IN HOLE	Water			
FLUID LEVEL				
SAMPLE SOURCE				
FLUID I.D. / C.I.C.				
TIME SINCE CIRC. STOP.				
RECORDED BY:	Drake & Wooddell			
OBSERVED:	Mr. Steve Chillson			


RUN #	PROBE TYPE / SN	MODULE TYPE / SN	LOGGING SPEED 10 ft./minute	AFTER SURVEY DEPTH ERROR	SAMPLE INTERVAL =	GAMMA COM-G11/4 CS01 F22	B. DENSITY CD-BD 21/B CS22 F22	NEUTRON COM-N11/A CS10 F22
						10 ft./minute	10 ft./minute	10 ft./minute
						0.2	0.2	0.2

COMMENTS:




RUN / PROBE TYPE / SN	GAMMA COM-G11/A	B. DENSITY CO-BD 21/B	NEUTRON COM-N11/A
MODULE TYPE / SN	CS01 F22	CS22 F22	CS10 F22
LOGGING SPEED	10 ft./minute	10 ft./minute	10 ft./minute
AFTER SURVEY DEPTH ERROR			
SAMPLE INTERVAL =	0.2	0.2	0.2

COMMENTS:



COMMENTS:





)

)

E

LANDFILL BORING LOGS

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch, Illinois**

DRILLING METHOD: **4 1/4" IDHSA**

BORING NO. **B1**

SHEET

SAMPLING METHOD: **2" OD SPLIT SPOON**

1 OF **1**

DRILLING

START TIME FINISH TIME

BORING LOCATION:

SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W

NORTHING **2115338.7** EASTING **1053435.5**

DATUM ELEVATION **774.7**

WATER LEVEL

TIME

DATE

CASING DEPTH

DATE **4/27/93** DATE **4/27/93**

DRILL RIG **CME 750 ATV**

SURFACE CONDITIONS **GRASS COVERED LANDFILL CAP**

ANGLE **Vertical** BEARING **-----**

SAMPLE HAMMER TORQUE FT-LBS

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS										
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS						
				FILL: Brown CLAY Over Black CLAY Cap Material														
5	769.7	4 6 7 6	92	1	FILL: Very Stiff Brown Clay, Gray Clay, White Plaster Like Material Over Brown and Black Peat Like Material	SS												3-4.5
	768.2	4 7 10 6	92	2	FILL: Refuse Over Brown and Black Clay Fill	SS												
	766.4	2 2 2 2	100	3	Brown Fine to Coarse SAND 4" Over Gray Fine to Coarse SAND	SS												
10	765.7	2 3 4 4	100	4	Fibrous PEAT (PT), Little Clay, Grades to Organic CLAY (OH)	SS												
	760.7	8 4 6 7	83	5		SS												
15		4 5 4 7	67	6	Loose Brown and Tan Fine to Coarse SAND (SP), Little Fine to Coarse Gravel and Silt	SS												
	757.7	3 7 8 8	92	7	Silty Fine to Medium SAND (SP), Little to Some Coarse Sand, Trace Fine Gravel	SS												
		5 8 5 9	92	8	Medium Dense Gray Fine to Coarse SAND (SP), Trace to Little Fine Gravel and Silt	SS												
20		4 4 5 9	42	9	Medium Dense Fine to Medium SAND and Some Silt (SP-SM), Trace to Little Fine Gravel and Coarse Sand to 20 Feet, Grades to Fine to Coarse SAND (SP), Trace to Little Fine Gravel	SS												
		5 7 6 6	46	10		SS												
25		10 15 16 18	58	11	Fine to Coarse SAND (SP-SM) Some Gravel, Trace Silt and Clay	SS												
		-	46	12	Grades to Medium SAND, Trace to Little Fine to Coarse Sand	SS												
	745.7	8 5 5 5	71	13	Grades to Fine to Coarse SAND and Fine Gravel	SS												1-1.5
30	743.7	4 6 7 7	100	14	Stiff Gray Sandy Silty CLAY to Clayey Silt (CL/ML) to Clayey Silty Sand (SM)	SS						31	15				1.75-2.75	
		3 3 3 4	75	15	Stiff to Very Stiff Gray Lean CLAY (CL) Little Fine to Coarse Sand, Trace Fine Gravel	SS												1.25-2
35	739.7				End of Boring at 35 Feet Boring Backfilled with Bentonite Slurry and Chips													

LOGGED BY **SJC**

DRILLING CONTR **E&F**

DATE **9/23/93**

CHK'D BY **DAP**

CHAS. MARKGRAF

ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. B2
		SHEET 1 OF 2
	SAMPLING METHOD: 2" OD SPLIT SPOON	
		DRILLING START TIME FINISH TIME
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W	WATER LEVEL: TIME	DATE
NORTHING 2115329.8 EASTING 1050990.5	DATE	DATE
DATUM ELEVATION 772.1	CASING DEPTH	4/26/93 4/27/93
DRILL RIG CME 750 ATV	SURFACE CONDITIONS	GRASS COVERED LANDFILL CAP
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
				FILL: Clay Cap Material to Approximately 4 Feet										
				Refuse to Approximately 10 Feet										
768.1														
5														
762.1														
10	2 3 1 1	67		1 Tan Fine to Coarse SAND (SP)	SS									
761.1				Peat and Organic CLAY (PT/OH)										
760.1	2 1 1 1	33		2 Soft Gray Fat CLAY (CH), Little to Some Sand, 1/4" Woody Peat Lense at 13.5 Feet	SS									
758.1	7 7 7 7	71		3 Medium Dense Fine to Coarse SAND (SP), Trace to Little, Fine Gravel	SS									
15														
756.1	6 5 7 6	71		4 Silty Fine to Coarse SAND (SM) 1" Silt Layer at 17 Feet	SS									
755.1				5 Medium Dense Fine to Coarse SAND (SP), Trace Fine Gravel	SS									
	3 6 10 12	25		Trace to Little Silt										
20	7 15 19 19	50		6 1/4" Silt Lenses at 21 and 21.9 Feet	SS									
	7 9 12 9	58		7 Grades to Fine to Coarse SAND (SP), Little to Some Fine Gravel	SS									
25	7 8 8 12	58		8 Grades to Fine to Medium SAND	SS									
	4 6 8 10	38		9 Grades to Fine to Coarse SAND and Fine GRAVEL (SP/GP)	SS									
30	4 5 7 10	54		10 Grades to Fine to Medium SAND (SP), Trace to Little Coarse Sand, Trace Gravel	SS									
	8 9 9 40	63		11 Fine to Medium SAND, Little Coarse Sand, Trace Fine Gravel	SS									
739.1	8 5 3 5	71		12 Stiff Gray Silty Sandy CLAY (CL) Grades to More Clayey Sand and Silt (CL/ML)	SS									1.25-2.5
35	5 6 6 6	71		13 Gray Sandy Silty CLAY (CL) Silt Lenses	SS							23	9	
	4 6 7 10	83		14	SS									1.5

LOGGED BY SJC	DRILLING CONTR E&F
DATE 9/22/93	CHK'D BY DAP
	CHAS. MARKGRAF

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
Illinois

DRILLING METHOD: **4 1/4" ID HSA**

BORING NO. **B2A**

SAMPLING METHOD: **2" OD SPLIT SPOON**

SHEET **1** OF **1**
 DRILLING

BORING LOCATION:

SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W

NORTHING **2115329.8**

EASTING **1051000.3**

DATUM

ELEVATION **772.1**

WATER LEVEL:

TIME

DATE

CASING DEPTH:

START TIME

FINISH DATE

4/27/93 4/27/93

DRILL RIG **CME 75**

SURFACE CONDITIONS **GRASS COVERED LANDFILL CAP**

ANGLE **Vertical**

BEARING **-----**

SAMPLE HAMMER TORQUE

FT-LBS

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS									
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS					
768.1				FILL: Brown Clay Cap Material, Blind Drilled to 15 Feet													
5				FILL: Refuse to 10 Feet, Logged from Cuttings													
762.1																	
10																	
15	12 11 13 12 100		1	Medium Dense Brown and Gray, Fine to Coarse SAND (SP), Some Gravel, Little Silt, Trace Clay	SS												
755.1				End of Boring at 17 Feet Boring Backfilled with Bentonite Chips													
20																	
25																	
30																	
35																	

LOGGED BY **PMS**

DRILLING CONTR **E & F**

DATE **9/22/93**

CHK'D BY **DAP**

CHAS. MARKGRAF

ID: WMI

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
Illinois

DRILLING METHOD: **4 1/4" IDHSA**

BORING NO. **B3**

SHEET

SAMPLING METHOD: **2" OD SPLIT SPOON 2.5" ID**

1 OF **2**

SPLIT SPOON 22'-24"; SHELBY TUBE 48"-50'

DRILLING

BORING LOCATION:

SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W

NORTHING **2115331.9**

EASTING **105115.3**

DATUM

ELEVATION **773.7**

CASING DEPTH

DATE **4/26/93**

DATE **4/26/93**

DRILL RIG **CME 750 ATV**

SURFACE CONDITIONS

GRASS COVERED LANDFILL CAP

ANGLE **Vertical**

BEARING **-----**

SAMPLE HAMMER TORQUE

FT-LBS

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS

5				FILL: Clay Cap Material to Approximately 4 Feet																	
	769.7			FILL: Refuse to Approximately 10.5 Feet																	
	10	763.2	5 4 5 3	38	1																
			1 1 2 2	33	2																
	15	758.7	2 3 7 8	67	3																
			5 6 8 8	58	4																
		754.7	5 2 1 1	67	5																
	20	753.7	5 8 10 8	50	6																
			7 17 18 15	75	7																
	25		5 6 10 11	58	8																
			5 6 13 10	25	9																
			4 5 6 6	79	10																
	30		6 8 9 9	42	11																
			6 7 8 9	50	12																
			6 8 9 10	63	13																
	35		12 8 8 8	67	14																

LOGGED BY **SJC**

DRILLING CONTR **E&F**

DATE **9/22/93**

CHK'D BY **DAP**

CHAS. MARKGRAF

ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. B4
		SHEET 1 OF 2
	SAMPLING METHOD: 2" OD SPLIT SPOON 2 1/2" ID	
	SPLIT SPOON 37'-39'	DRILLING START TIME FINISH TIME
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W	WATER LEVEL	DATE DATE
NORTHING 2115328.1 EASTING 1051350.4	DATE	DATE DATE
DATUM	ELEVATION 774.1	CASING DEPTH
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED LANDFILL CAP	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
				FILL: Blind Drilled to 5 Feet Brown and Black Clay Cap Material										
770.1	2 10 6 4	25	1	FILL: Refuse Paper, Metal, Plastic, Etc.	SS									
10	5 7 3 4	17	2	FILL: Refuse Concrete, Paper, Plastic, Metal, Etc.	SS									
760.6														
15	3 7 7 8	67	3	Medium Dense Tan Fine Silty SAND to Fine Sandy SILT (SM)	SS									
757.6	5 7 8 9	71	4	Medium Dense Gray Fine SAND (SP), Trace to Little SILT	SS									
20	3 4 5 7	75	5	Loose Brown Fine SAND (SP), Trace Silt, Trace to Little Medium Sand	SS									
	4 5 6 7	71	6	Medium Dense Brown Fine to Medium SAND	SS									
	3 4 6 8	54	7	Grades to Fine to Coarse SAND and Fine GRAVEL (SP/GP)	SS									
25	5 7 7 7	67	8	Fine to Coarse SAND (SP), Little Fine Gravel	SS									
	2 5 7 8	75	9		SS									
30	-	75	10	Sand Grades Fine to Coarse	SB									
	8 8 8 10	67	11	Medium Dense Gray Fine to Medium SAND (SP)	SS									
	6 10 11 13	88	12	SILT and SAND (SP/ML)	SS									
35	5 7 8 8	71	13	Medium Dense Fine Sandy SILT to Silty SAND (SM), Silt	SS									

LOGGED BY SJC	DRILLING CONTR E&F
DATE 9/22/93	CHK'D BY DAP
	CHAS. MARKGRAF

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" IDHSA	BORING NO. B5
		SHEET 1 OF 2
	SAMPLING METHOD: 2" OD SPLIT SPOON	DRILLING START TIME: _____ FINISH TIME: _____
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8, T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	DATE: 4/23/93 DATE: 4/23/93
NORTHING 211544.5 EASTING 1051463.4	CASING DEPTH	
DATUM _____ ELEVATION 775.2	SURFACE CONDITIONS GRASS COVERED LANDFILL CAP	
DRILL RIG CME 750 ATV	ANGLE Vertical BEARING -----	
SAMPLE HAMMER TORQUE _____ FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
				FILL: Brown Clay Cap Material to 5 Feet Blind Drilled to 10 Feet										
5				FILL: Refuse and Clay										
10	5 8 5 12	25	1	FILL: Refuse	SS									
15	6 6 6 12	13	2		SS									
758.2	5 10 11 12	79	3	Refuse, Little Sand in Tip of Spoon	SS									
20	5 6 11 12	63	4	Medium Dense Fine to Medium SAND (SP), Trace to Little Clayey Sand	SS									
25	5 2 1 1	46	5	2" Organic Sandy Clay, Wood Fibers in End of Spoon	SS									
	5 12 13 16	25	6		SS									
	5 8 10 9	50	7	Medium Dense Fine to Medium SAND (SP) Grades to Fine to Coarse Little Fine Gravel, Little Clay	SS									
	3 6 9 10	71	8	Medium Dense Fine to Coarse SAND (SP), Little Fine Gravel	SS									
30	5 7 8 8	83	9	Fine to Coarse Sand, Some Gravel, Little Silt, Trace Clay	SS									
	10 9 10 10	67	10	Grades to Medium Dense Fine SAND (SP), Less Coarse Sand, Grades Back to Fine to Coarse Sand	SS									
	6 9 11 14	67	11		SS									
740.2	7 10 10 11	67	12	3" Gray Clayey Silt Layer Over Fine Silty SAND (SM), Grades to Fine to Coarse Sand in Tip of Spoon	SS									

LOGGED BY SJC	DRILLING CONTR E&F	
DATE 9/22/93	CHK'D BY DAP	CHAS. MARKGRAF
		ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
 Illinois

SHEET **2** OF **2**

BORING NO. **B5**

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS					
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS	
3	10	10	75	13. Fine Silty SAND (SM)	SS								
4	5	7	6	58	14. Fine Silty SAND to Fine SAND (SM/SF), Trace to Some Silt	SS							
6	11	10	10	63	15. Fine Silty SAND (SM)	SS							
7	7	3	4	58	16. Grades to Silt in Tip of Spoon 6+ Fine to Coarse Sand and Silt, Trace Fine Gravel Very Silty Gray Silty CLAY (CL)	SS							
8	8	10	12	100	17. Silty Gray Silty CLAY (CL), Little Fine to Coarse Sand, Shale Fragments Present	SS			29	13	1.25- 1.250		
9	4	6	9	100	18. End of Boring at 49 Feet Boring Backfilled with Bentonite Slurry and Churns	SS					1.25- 1.25		

85

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

F

GEOTECHNICAL LABORATORY DATA



LABORATORY RESULTS

Project: HOD Landfill

Project #: 10010201

Location: Antioch, Illinois

<u>Sample Number</u>	<u>Description</u>	<u>Liquid Limit %</u>	<u>Plasticity Index %</u>	<u>Natural Moisture %</u>
6764-0001	HD-SU01-01	28	12	27.8
6764-0002	HD-SU02-01	33	8	28.3
6764-0003	HD-SU03-01	51	21	44.2
6764-0004	HD-SU04-01	26	10	24.0
6764-0005	HD-SU04-91	25	9	22.7
6764-0006	HD-SU05-01	29	12	18.5



MADISON
ONE SCIENCE COURT
P.O. BOX 556
MADISON, IN 47101
TEL: 317-251-1111
FAX: 317-251-1177

LABORATORY RESULTS

Project: HOD Landfill RI/FS

Project #: 10010201

Location: Antioch, Illinois

<u>Sample Number</u>	<u>Description</u>	<u>Loss on Ignition %</u>	<u>Estimated Total Porosity</u>
6619-0006	HD-SSW3D-38	1.64	0.24

Ck'd: *JMF* App'd: DTL
Date Issued: 6-4-93



LABORATORY RESULTS

Project: HOD Landfill RI/FS

Project #: 10010201

Location: Antioch, Illinois

<u>Sample Number</u>	<u>Description</u>	<u>Loss on Ignition %</u>	<u>Estimated Total Porosity</u>
6877-0008	HD-SSW2D-31	3.6	0.38
6878-0006	HD-SSW5S-9	11.7	--

-- Not requested.

Ck'd: *SR* App'd: *VJR*
Date Issued: *6-16-93*

FALLING HEAD PERMEABILITY TEST

arsyn Inc., 1 Science Court, Madison, WI 53711 Phone: (608) 231-6955 or 231-4747

PROJECT: H.O.D. LANDFILL RI/PS
STATION: Antioch, Illinois

SAMPLE: HD-SSW20-31
DEPTH (ft):

SOIL DESCRIPTION (a): Gray Lean CLAY (CL)

SAMPLE DIAMETER (cm) 7.4
SAMPLE AREA, A (cm²) 42.6

	<u>INITIAL</u>	<u>FINAL</u>
SAMPLE LENGTH, L (cm)	18.0	17.6
MOISTURE CONTENT, %	21.6	20.9
DRY DENSITY (lb/cu ft)	104.9	106.1
PERCENT COMPACTION	-	-

COEFFICIENT OF PERMEABILITY, k (cm/sec)

RUN	COEFFICIENT OF PERMEABILITY, k (cm/sec)
1	1.3E-08
2	1.5E-08
3	1.4E-08
4	1.7E-08
5	1.6E-08
6	1.3E-08
7	1.6E-08
8	1.8E-08
9	1.3E-08
10	1.6E-08

AVERAGE COEFFICIENT OF PERMEABILITY = 1.5E-08 cm/sec
(Based on run numbers 8 through 10)

2.3aL h₀
GI (LA): k = ----- log₁₀ ---, Where A = cross-sectional area of standpipe,
At h₁ t = time for water level to fall from initial height, h₀, to final height, h₁
(All other terms are defined above)

REMARKS: (a) Visual Soil Description.

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter Shelby tube sample.

CHECKED BY: CS DATE: 5-26-93 APPROVED BY: DTL DATE: 6-8-93

DATE: 5/27/93

WILLIAMS HEAD PERMEABILITY TEST

3000 In., Science Court, Madison, WI 53711 Phone: (608) 231-6555 or 231-4747

PROJECT LOCATION: H.O.D. RANDALL FIVE Antioch, Illinois

SAMPLE IDENTIFICATION: HD-88W3D-38

SOIL DESCRIPTION (a): Gray Lean CLAY, Some Sand, Little Gravel (CL)

SAMPLE DIAMETER (cm): 7.4
SAMPLE AREA, A (cm²): 42.6

	INITIAL	FINAL
SAMPLE LENGTH, L (cm)	18.7	18.6
MOISTURE CONTENT, %	11.7	11.6
WET DENSITY (lb/cu ft)	127.4	127.9
PERCENT COMPACTION	-	-

RUN	COEFFICIENT OF PERMEABILITY, k (cm/sec)
1	1.9E-08
2	1.6E-08
3	1.5E-08
4	1.6E-08
5	1.9E-08
6	2.0E-08
7	1.4E-08
8	1.7E-08
9	1.7E-08
10	1.7E-08

AVERAGE COEFFICIENT OF PERMEABILITY = 1.7E-08 cm/sec
(Based on run numbers 8 through 10)


FORMULA: $k = \frac{2.3al}{t} \log_{10} \frac{h_0}{h_1}$, where a = cross-sectional area of standpipe, At h₀ = t = time for water level to fall from initial height, h₀ to final height, h₁ (All other terms are defined above)

COMMENTS: (a) Visual Soil Description

REMARKS: This permeability test was performed on a relatively undisturbed 3-inch diameter Shelby tube sample.

APPROVED BY: CLS DATE: 5/21/93 APPROVED BY: DTL DATE: 5/27/93

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	20.6	20.1	28.1	31.2

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
28	12	9.66	0.09	0.02	0.005				

MATERIAL DESCRIPTION	USCS
O Gray Lean CLAY, Some Gravel and Sand	CL

<p>Project No.: 10010201 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois O Sample: HD-SUB1-01</p> <p>Date: 5/27/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks:</p> <p>TESTED BY CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p> <p>Sheet No. _____</p>
---	--

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	4.9	32.4	47.0	15.7

	LL	PI	D ₂₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	33	8	0.87		0.06	0.028	0.0046	0.0024	4.62	29.9

MATERIAL DESCRIPTION	USCS
O Gray Lean CLAY, Some Sand, Trace Gravel	CL


Project No.: 10010201
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SU02-01
 Date: 5/27/93

Remarks:
 TESTED BY CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	3.0	25.5	43.2	28.3

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	51	21	0.31		0.02	0.005				

MATERIAL DESCRIPTION	USCS
○ Gray-Brown Elastic SILT, Some Clay and Sand, Trace Gravel	MH

<p>Project No.: 10010201 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HI-SU03-01</p> <p>Date: 5/27/93</p>	<p>Remarks: TESTED BY CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p>
<p>GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	
<p>Sheet No.</p>	

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	0.5	60.5	23.2	15.8

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○ 26	10	0.47	0.28	0.21	0.043	0.0041	0.0023	2.88	123.0

MATERIAL DESCRIPTION	USCS
○ Brown Clayey SAND, Trace Gravel	SC


Project No.: 10010201
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SU04-01
 Date: 5/27/93

Remarks:
 TESTED BY CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
 WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
o	0.0	1.2	62.0	20.6	16.2

LL	PI	D85	D60	D50	D30	D15	D10	Cc	Cu
25	9	0.48	0.29	0.23	0.044	0.0043	0.0014	4.62	202.1

MATERIAL DESCRIPTION	USCS
o Brown Clayey SAND, Trace Gravel	SC

Project No.: 10010201
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 o Sample: HD-SU04-91


Remarks:
 TESTED BY CLS
 CHECKED BY CLS
 APPROVED BY DTL

Date: 5/27/93

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	6.6	33.1	33.5	26.8

LL	PI	D85	D60	D50	D30	D15	D10	Cc	Cu
○ 29	12	1.26		0.03	0.006				

MATERIAL DESCRIPTION	USCS
○ Gray-Brown Lean CLAY, Some Sand, Little Gravel	CL

Project No.: 10010201
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 ○ Sample: HD-SU05-01


Date: 5/27/93

Remarks:
 TESTED BY CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	0.6	10.8	54.8	33.8

LL	PI	D ₂₅	D ₅₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
38	11			0.01	0.004				

MATERIAL DESCRIPTION	USCS
0 Brown Lean CLAY, Little Sand, Trace Gravel	CL

Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois Sample: HD-SSW2D-9 Date: 5/24/93	Remarks: TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i>
GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.	
Sheet No.	

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	3.3	2.3	33.3	61.1

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	38	19		0.00					

MATERIAL DESCRIPTION	USCS
O Brown Lean CLAY, Trace Gravel and Sand	CL

Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SSW2D-34


Date: 5/20/93

Remarks:
 TESTED BY TWP
 CHECKED BY *CS*
 APPROVED BY DTL

GRAIN SIZE DISTRIBUTION TEST REPORT
 WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	0.1	2.0	33.4	64.5

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	38	19			0.00					

MATERIAL DESCRIPTION	USCS
○ Brown Lean CLAY, Trace Sand	CL

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSW2D-934</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks: TESTED BY TWP/CLS CHECKED BY <i>CS</i> APPROVED BY <i>DTL</i></p> <p>Sheet No.</p>
---	---

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	15.3	78.0	5.1	1.6

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	--	--	5.13	0.61	0.51	0.369	0.2355	0.1574	1.43	3.8

MATERIAL DESCRIPTION	USCS
0 Brown Fine-Coarse SAND, Some Gravel, Little Silt, Trace Clay	SP-SM


Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 0 Sample: HD-SSW2D-88
 Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	10.4	80.7	5.7	3.2

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	--	3.00	0.64	0.45	0.230	0.1690	0.0940	1.20	6.8

MATERIAL DESCRIPTION	USCS
○ Gray-Brown Fine-Coarse SAND, Little Gravel & Silt, Trace Clay	SW-SM

Project No.: 10010201/38140
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 ○ Sample: Boring HD-SSW3SB-20


 Date: 4/28/93

Remarks:
 TESTED BY CLS
 CHECKED BY CLS
 APPROVED BY DTL

GRAIN SIZE DISTRIBUTION TEST REPORT
 WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	5.0	44.0	28.8	22.2

LL	PI	D ₉₅	D ₈₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	18	6	1.00	0.15	0.07	0.010	0.0017		

MATERIAL DESCRIPTION	USCS
O Gray-Brown Sandy Silty CLAY, Trace Gravel	CL-ML

<p>Project No.: 10010201/38140</p> <p>Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois</p> <p>Sample: Boring HD-SSW3B-40</p> <p>Date: 4/28/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks:</p> <p>TESTED BY CLS</p> <p>CHECKED BY <i>CLS</i></p> <p>APPROVED BY <i>DTL</i></p> <p>Sheet No. _____</p>
--	--

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	18.5	41.4	30.6	9.5

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	63	NP	7.00	0.40	0.25	0.050	0.0127	0.0054	1.16	75.0

MATERIAL DESCRIPTION	USCS
○ Brown Silty Fine-Coarse SAND, Some Gravel, Little Clay (Organic Content = 11.7%)	SM

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSW5S-9</p> <p>Date: 5/26/93</p>	<p>Remarks:</p> <p>TESTED BY TWP/CLS CHECKED BY <i>CS</i> APPROVED BY <i>DTL</i></p>
<p>GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	
<p>Sheet No.</p>	

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	8.8	70.6	16.5	4.1

	LL	PI	D ₂₅	D ₅₀	D ₆₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	--	--	3.20	0.72	0.41	0.180	0.0589	0.0462	0.97	15.7

MATERIAL DESCRIPTION	USCS
0 Brown Fine-Coarse SAND, Some Silt, Little Gravel, Trace Clay	SM

Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SSW5S-14


 Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY CLS
 APPROVED BY DTL

 Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT
 WARZYN, INC.

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	0.0	87.6	9.9	2.5

LL	PI	D ₉₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u	
○	--	--	0.57	0.34	0.20	0.167	0.0854	0.0626	1.29	5.5

MATERIAL DESCRIPTION	USCS
○ Brown Fine-Medium SAND, Little Silt, Trace Clay	SM

Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSW6S-14 Date: 5/24/93	Remarks: TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i>
GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.	
Sheet No. _____	

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	0.0	10.5	55.5	34.0


LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
33	14			0.01	0.004				

MATERIAL DESCRIPTION	USCS
O Gray-Brown Lean CLAY, Little Sand	CL

Project No.: 10010201/38140
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: Boring HD-SSW7D-4
 Date: 4/28/93

Remarks:
 TESTED BY CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	0.9	96.9	0.3	1.9

LL	PI	D ₈₅	D ₈₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
--	--	0.58	0.43	0.39	0.296	0.2270	0.2018	1.01	2.1

MATERIAL DESCRIPTION	USCS
0 Gray-Brown Fine-Medium SAND, Trace Clay, Gravel and Silt	SP

Project No.: 10010201/38140
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: Boring HI-SSW7D-94


Remarks:
 TESTED BY CLS
 CHECKED BY *CS*
 APPROVED BY *DTL*

Date: 4/28/93

GRAIN SIZE DISTRIBUTION TEST REPORT
 - WARZYN, INC.

Sheet No.

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	1.4	4.1	32.8	61.7

	LL	PI	D ₃₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	34	15			0.00					

MATERIAL DESCRIPTION	USCS
0 Gray-Brown Lean CLAY, Trace Sand and Gravel	CL

Project No.: 10010201/38140
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 0 Sample: Boring HD-SSW7D-29


 Date: 4/28/93

Remarks:
 TESTED BY CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	30.5	62.8	4.3	2.4

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
--	--	13.85	2.11	0.82	0.327	0.2131	0.1598	0.32	13.2

MATERIAL DESCRIPTION	USCS
0 Brown Fine-Coarse SAND, Some Gravel, Trace Silt and Clay	SP-SM


Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SSB1-27
 Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY *CLS*
 APPROVED BY DTL

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	0.7	7.9	43.7	47.7

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	31	15			0.01	0.001				

MATERIAL DESCRIPTION	USCS
O Brown Lean CLAY, Little Sand, Trace Gravel	CL

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois Sample: HD-SSB1-33</p> <p>Date: 5/24/93</p>	<p>Remarks:</p> <p>TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p>
<p>GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Sheet No. _____</p>

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
C	0.0	18.3	73.9	5.7	2.1

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _u	C _l
C	—	—	6.17	0.90	0.52	0.289	0.1429	0.0944	0.85	9.5

MATERIAL DESCRIPTION	USCS
○ Brown Fine-Coarse SAND, Some Gravel, Little Silt, Trace Clay	SP-SM

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSB2A-17</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks:</p> <p>TESTED BY TWP/CLS</p> <p>CHECKED BY <i>CLS</i></p> <p>APPROVED BY <i>DTL</i></p> <p style="text-align: center;">Sheet No.</p>
--	--

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	7.9	21.1	38.5	32.5

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
○	23	9	0.65		0.02	0.004				

MATERIAL DESCRIPTION	USCS
○ Brown Lean CLAY, Some Sand, Little Gravel	CL

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSB2-36</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks: TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p> <p>Sheet No.</p>
---	--

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	18.2	67.6	10.5	3.7

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	--	5.69	1.38	0.68	0.243	0.0794	0.0562	0.76	24.5

MATERIAL DESCRIPTION	USCS
O Brown Fine-Coarse SAND, Some Gravel, Little Silt, Trace Clay	SM

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois O Sample: HD-SSB3-24</p> <p>Date: 5/24/93</p>	<p>Remarks: TESTED BY TWP/CLS CHECKED BY CLS APPROVED BY DTL</p>
GRAIN SIZE DISTRIBUTION TEST REPORT WARZYH, INC.	
Sheet No.	

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	0.7	11.2	43.3	44.8

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	27	12			0.01	0.002				

MATERIAL DESCRIPTION	USCS
0 Brown Lean CLAY, Little Sand, Trace Gravel	CL

Project No.: 10010201/30133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 Sample: HD-SSE3-48


 Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
 WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	2.3	70.4	23.5	3.8

LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
--	--	0.28	0.18	0.15	0.083	0.0426	0.0291	1.29	6.3

MATERIAL DESCRIPTION	USCS
O Brown Fine SAND, Some Silt, Trace Clay and Gravel	SM


Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 O Sample: HD-SSB4-39
 Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY *CLS*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No. _____

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	1.1	67.7	27.6	3.6

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	--	--	0.24	0.15	0.13	0.071	0.0395	0.0296	1.13	5.1

MATERIAL DESCRIPTION	USCS
0 Brown Fine SAND; Some Silt; Trace Clay and Gravel	SM

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois Sample: HD-SSB4-939</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks: TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY DTL</p> <p>Sheet No.</p>
--	---

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
O	0.0	0.9	7.7	52.3	39.1

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
O	25	11			0.01	0.003				

MATERIAL DESCRIPTION	USCS
O Brown Lean CLAY, Little Sand, Trace Gravel	CL

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois O Sample: HD-SSB4-49</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks:</p> <p>TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p> <p>Sheet No.</p>
---	--

GRAIN SIZE DISTRIBUTION TEST REPORT




Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
○	0.0	17.3	69.5	8.8	4.4

LL	PI	D ₈₅	D ₈₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
—	—	5.56	1.36	0.81	0.309	0.1175	0.0432	1.62	31.6

MATERIAL DESCRIPTION	USCS
○ Brown Fine-Coarse SAND, Some Gravel, Little Silt, Trace Clay	SM

<p>Project No.: 10010201/38133 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois ○ Sample: HD-SSB5-31</p> <p>Date: 5/24/93</p> <p style="text-align: center;">GRAIN SIZE DISTRIBUTION TEST REPORT WARZYN, INC.</p>	<p>Remarks: TESTED BY TWP/CLS CHECKED BY <i>CLS</i> APPROVED BY <i>DTL</i></p> <p>Sheet No. _____</p>
---	--

GRAIN SIZE DISTRIBUTION TEST REPORT



Symbol	% +3"	% GRAVEL	% SAND	% SILT	% CLAY
0	0.0	0.4	8.5	42.4	48.7

	LL	PI	D ₈₅	D ₆₀	D ₅₀	D ₃₀	D ₁₅	D ₁₀	C _c	C _u
0	29	13			0.01	0.002				

MATERIAL DESCRIPTION	USCS
○ Brown Lean CLAY, Little Sand	CL

Project No.: 10010201/38133
 Project: H.O.D. LANDFILL RI/FS, Antioch, Illinois
 ○ Sample: HD-SSB5-47

Date: 5/24/93

Remarks:
 TESTED BY TWP/CLS
 CHECKED BY *US*
 APPROVED BY *DTL*

GRAIN SIZE DISTRIBUTION TEST REPORT
WARZYN, INC.

Sheet No.

G

DEVELOPMENT AND ENVIRONMENTAL
HISTORY OF SEQUOIT ACRES
INDUSTRIAL PARK

G

SUMMARY OF ENVIRONMENTAL HISTORY OF SEQUOIT ACRES INDUSTRIAL PARK THROUGH 1989

The Sequoit Acres Industrial Park, which is located west of the site on the western bank of Sequoit Creek, contains several companies which are RCRA small quantity hazardous waste generators, five registered underground storage tanks, and fill areas that were, at least in part, waste dumps (the Cunningham Dump and the Quaker Dump). The status of waste storage and disposal activities practiced by the small quantity generators prior to RCRA is not known. Figure 7 of the main text shows the locations of these facilities. The following discussion of the industrial park is based on an environmental audit conducted by Patrick Engineering, Inc. (Patrick Engineering, 1989).

LANDFILLING ACTIVITIES

West of the H.O.D. Landfill, on the eastern portions of the Sequoit Acres Industrial Park, the naturally low lying areas were filled as part of a dump operation. Filling began south of the bend in McMillen Road, in the area that now makes up the Quaker Industries parking lot. Other areas along Sequoit Avenue and Anita Avenue have also been filled for industrial development (see Figure 8 of main text). The makeup of the fill in these areas is unknown.

Possibly of as early as 1959, north of McMillen Road and adjacent to and west of H.O.D. Landfill, waste disposal occurred in the Cunningham Dump operated on land owned by Quaker Industries. It has been reported that this dump was open for dumping of any material, and in general there was no supervision of dumping

activities. Combustible materials were periodically burned. Private waste disposal on the Quaker property, which is in the same general area as the Cunningham Dump, continued until 1965. The exact location of this disposal area is not known. This operation and disposal areas will be referred to as the Quaker Dump. Figure 8 of the main text shows the filled and landfilled areas in Sequoit Acres Industrial Park.

QUAKER INDUSTRIES

Quaker Industries, Inc. (Quaker) is a manufacturer of wood and metal tray tables. Quaker is currently located south of McMillen Road, but Quaker also formerly owned land north of McMillen Road and west of Sequoit Creek that was used as the Cunningham Dump in the early 1960s. After landfilling started at the H.O.D. Landfill, Quaker built a storage warehouse over the location of the closed Cunningham Dump. Quaker sold this warehouse to Malnekoff Closeouts in 1987.

Potentially, hazardous wastes generated from Quaker's operations include: paint thinners, sludges, and lacquers. This statement is based on information provided by Quaker to U.S. EPA. Supplemental disposal permits obtained by the H.O.D. Landfill allowed the site to dispose of Quaker paints, coolants, paint booth oversprays, and water soluble oils and stains.

A January 30, 1968 letter from Applied Engineering Company (consultant to the Village of Antioch) to the State of Illinois Sanitary Board, indicated that Quaker discharged untreated industrial effluent to the wetlands in this area which discharged to Sequoit Creek. Attached to the letter was a summary of chemicals used in Quaker's manufacturing processes at that time. This correspondence is included at the end of this Appendix. The chemicals used by Quaker included paint strippers containing chlorinated hydrocarbons. This effluent was discharged to Sequoit Creek and the nearby wetlands via an existing discharge pipe located near the southwestern corner of the H.O.D. Landfill Site. It is unclear for how long of time the discharge occurred. Prior to the rerouting of Sequoit Creek, the area to the east of McMillen Road was wetlands. It is likely that at the time the surface water flow in this area was toward the east and northeast, across the area now occupied by the H.O.D. Landfill, to Sequoit Creek. Therefore, there was the potential for the discharge from Quaker to spread over a relatively large area of the present H.O.D. site. The area of this effluent discharge overlies the surficial sand, and the Quaker effluent, which included chlorinated hydrocarbons, potentially moved downward into the surficial sand.

The State of Illinois Sanitary Board replied in their February 15, 1968 letter to Applied Engineering, that this discharge of untreated waste was not acceptable.

An NPDES permit for Quaker's non-contact cooling water discharge was issued in 1974. Quaker currently maintains this NPDES permit for their discharge of approximately 30,000 gallons per day (gpd) of non-contact cooling water to Sequoit Creek.

Quaker has stored drums containing hazardous waste on their property. Review of aerial photographs taken over the period 1980-1981 indicated that several dozen 55-gallon drums were present at that time (Patrick Engineering, 1989). In 1980, Quaker applied for a RCRA permit for their storage of hazardous wastes. This permit application was withdrawn in 1983. In 1984, the U.S. EPA informed Quaker that they were a small quantity generator and that they were not required to obtain a RCRA permit (Patrick Engineering, 1989).

Other potential contamination sources include floor drains within Quaker's manufacturing facility, Quaker's discharge to the sanitary sewer, and Quaker's air emissions. Solvents were used in Quaker's manufacturing processes and may have entered the facility's floor drains and/or sanitary sewer. The sewer line serving Quaker's facility runs north from the facility along Anita Avenue. Quaker's facility uses hot and cold solvent processes and, until 1980, discharged VOCs into the air.

Quaker historically has had underground storage tanks (USTs) on their property. A 10,000-gallon steel UST containing oil was installed in approximately 1961 and was removed in 1989. The 10,000-gallon tank was removed by Quaker because it was no longer needed. A 200,000-gallon concrete UST for water was installed by Quaker in 1964. This water tank was necessary for the operation of a sprinkler system at the Quaker factory, and was last used in 1975. Another steel UST (500 to 750 gallons) is reportedly currently used at the Quaker for storage of used oil and/or water (Patrick Engineering, 1989).

ANTIOCH TOWNSHIP HIGHWAY DEPARTMENT

The Antioch Township Highway Department (the Department) is responsible for maintaining the township's roads. The Department performs truck maintenance, and uses fuels, road salts, paints, and solvents.

The Department has three registered USTs. A 4,000-gallon unlined steel UST is used for gasoline storage and a 1,000-gallon unlined steel UST is used for diesel fuel storage. These two USTs were painted externally before they were installed to resist corrosion. The third UST on the Department's property has not been used since August 1983 and is of an unspecified size. This unlined UST was

apparently used for gasoline storage, and it is not known if this UST was painted externally prior to installation to resist corrosion.

CHICAGO INK AND RESEARCH COMPANY, INC.

Chicago Ink and Research Company, Inc. (Chicago Ink) manufactures industrial inks. Chicago Ink has been operating in the Sequoit Acres Industrial Park since 1956. Hazardous wastes generated by Chicago Ink may include the following: solvent washes and sludges, caustic washes and sludges, and water washes and sludges generated from cleaning the equipment that is used in the production of ink from pigments; soaps, and stabilizers containing chromium and lead (Patrick Engineering, 1989). Chicago Ink has a registered 60-gallon UST that is both internally lined and externally painted to resist corrosion. The present contents and use, if any, of this tank is unknown.

GALDINE ELECTRONICS, INC.

Galdine Electronics, Inc. is a manufacturer of printed electronic circuit boards and has operated at their current location in the Sequoit Acres Industrial Park for approximately 21 years. Hazardous wastes generated by Galdine Electronics include: methylene chloride, a hydrochloric acid mixture, a chromic acid solution, a plating sludge, and a flammable liquid waste (Patrick Engineering, 1989). Rinse water from Galdine Electronics' manufacturing processes and currently discharged into the Village of Antioch's sanitary sewer system for treatment at the Village of Antioch's Publically Owned Treatment Works (POTW).

MAJOR INDUSTRIAL TRUCK, INC.

Major Industrial Truck, Inc. is concerned with the sales, service, and rental of forklifts and has been at their current location in the Sequoit Acres Industrial Park for approximately 9 years. They are a service company and do not manufacture any products on-site. In September 1988, Major Industrial Truck notified the IEPA that they would be shipping the small quantity of ignitable hazardous waste which they generated to Safety Kleen Corporation in Elgin, Illinois (Patrick Engineering, 1989).

NU-WAY SPEAKER PRODUCTS, INC.

Nu-Way Speaker Products, Inc. (Nu-Way) is a manufacturer of non-metallic components for loudspeakers and has been in business at their current location in the Sequoit Acres Industrial Park for approximately 14 years. Hazardous materials that are generated by Nu-Way's manufacturing process are acetone and phenol (Patrick Engineering, 1989).

NCG ELECTRONICS, INC.

NCG Electronics, Inc., was an affiliate of Galdine Electronics, Inc. and once occupied a building in the Sequoit Acres Industrial Park. NCG Electronics was also a manufacturer of printed circuit boards. A spent copper etching solution, a by-product of their manufacturing process classified as non-hazardous was generated by NCG Electronics (Patrick Engineering, 1989).

ROLL FOIL LAMINATING, INC.

No information was available regarding the manufacturing processes at this facility. In March 1987, a Notification of Hazardous Waste Activity report was filed by Roll Foil Laminating, Inc. with the U.S. EPA indicating that they generate less than 1000 kilograms per month of F003 and F005 non-halogenated solvents (Patrick Engineering, 1989).

REFERENCE

Patrick Engineering, Inc., 1989. *Environmental Audit of Sequoit Acres Industrial Park*. Antioch, Illinois.

AJS/njt/RHW
[chi 609 9/e]
10010201

H

GROUNDWATER MONITORING WELL
BORING LOGS AND
WELL CONSTRUCTION DETAILS

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W2D
		SHEET 1 OF 2
	SAMPLING METHOD: 5' CME SAMPLING TUBE 2" OD SPLIT SPOON (84-88 FT)	DRILLING START TIME: _____ FINISH TIME: _____
BORING LOCATION: SE 1/4 of SE 1/4 of Section 17, T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	DATE: 4/17/93 DATE: 4/17/93
NORTHING 2116648.2 EASTING 1052499.9	DATE: _____ DATE: _____	
DATUM _____ ELEVATION 770.7	CASING DEPTH _____	
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED PRAIRIE	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE _____ FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS					
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS	
769.2	1	75	[Symbol]	1 Stiff to Very Stiff Reddish Brown Organic Top Soil (OH), Roots to 1 ft then Brown Silty Sandy Clay	SB								1- 3.5
766.7 765.7	5	83	[Symbol]	2 Soft to Stiff Brown and Gray Mottled Clayey SILT to Silty CLAY (ML/CL) Grades to more silty CLAY (CL) Trace to Little Fine to Coarse Sand and Fine Gravel, Sand Pocket at 9 Ft	SB			30	11				25- 1.0
761.7 760.7	10	75	[Symbol]	3 Brown SAND Layer (SP) Brown Silty CLAY (CL) to 11.5'	SB								2- >4.5
759.2 756.7	15	100	[Symbol]	4 Gray Silty CLAY (CL), Little to Some Fine to Coarse Sand, Trace to Little, Fine to Coarse Gravel, Sand Lens at 12' and 14', Shale Fragments Present Gravelly Stiff to Very Stiff Gray Silty CLAY (CL)	SB								1.5- 4.0
752.7	20	95	[Symbol]	5 Gray Very Stiff Lean CLAY (CL), Little to Some Silt, Trace to Little Gravel and Fine to Coarse Sand Gray Stiff to Very Stiff Lean CLAY (CL) Little to Some Silt, Trace to Little Fine to Coarse Sand, Trace Fine Gravel	SB								2.5- 3.0
	25	95	[Symbol]	6	SB								1.5- 2.5
	30	90	[Symbol]	7 Shelby Tube 29 - 31' Shale Fragments Present	SB				38	19			1.5- 2.5
	35	100	[Symbol]	8 Lean Clay (CL) Trace Gravel and Sand	SB								1- 2.5
		93	[Symbol]	9	SB								1.5-

LOGGED BY SJC	DRILLING CONTR E & F	
DATE 9/17/93	CHK'D BY DAP	CHAS. MARKGRAF

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W3SA
SAMPLING METHOD: 2" OD SPLIT SPOON		SHEET 1 OF 1
BORING LOCATION: NE 1/4 of NE 1/4 of Section 17, T 46 N, R 10 E/W		DRILLING START TIME FINISH TIME
NORTHING 2115185.3	EASTING 1051029.2	DATE DATE DATE
DATUM	ELEVATION 763.8	CASING DEPTH 4/6/93 4/6/93
DRILL RIG CME 750 ATV	SURFACE CONDITIONS MARSH/WETLAND, SURFACE WATER	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
631.1	67			1 Frozen Black Muck - Peaty, Vegetation Debris (PT)	SS									
WT	75			2 Greenish Light Gray Soft Clay (OH) Silt Lenses Vegetation Debris, Gastropod Shells and Other Shell Material Present, Spongy Peat Like	SS									
758.8	5411	83		3 Very Loose Light Gray Fine SAND to Silty Sand (SP/SM), Some Medium, Trace Coarse Sand Little to Some Silt	SS									
5.5	46			4	SS									
755.7	5544	83		5 Greenish Soft Clay (CH) Trace Silt, Gastropod Shells Present	SS									
754.8	2346	66		6 Very Loose Gray Fine to Coarse SAND and Fine GRAVEL (SP/GP), Grades to Coarse to Fine to Coarse	SS									
	2245	92		7	SS									
	57913	75		8 Medium SAND (SP) to 13.5 Feet Grades to Medium to Coarse Sand	SS									
747.8				Trace Fine Gravel										
				End of Boring at 16 Feet Monitoring Well Set at 15.64' PID = None Detected										

LOGGED BY SJC	DRILLING CONTR E & F
DATE 9/22/93	CHK'D BY DAP
	CHAS. MARKGRAF

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4 ID HSA	BORING NO. W3SB
		SHEET 1 OF 1
	SAMPLING METHOD: 2" OD SPLIT SPOON	DRILLING START TIME: _____ FINISH TIME: _____
BORING LOCATION: NE 1/4 of NE 1/4 of Section 17, T 46 N, R 10 E/W	WATER LEVEL TIME: _____ DATE: _____	CASING DEPTH 4/7/93 4/7/93
NORTHING 2115189.4 EASTING 1051027.8	SURFACE CONDITIONS MARSH/WETLAND, SURFACE WATER	
DATUM _____ ELEVATION 763.7	ANGLE Vertical BEARING -----	
DRILL RIG CME 750 ATV	SAMPLE HAMMER TORQUE _____ FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS						
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS		
				Blind Drill to 16 Feet See Boring Log W3SA for Geologic Description to 16 Feet										
747.7	WT/12"	100		1 Loose Gray Fine to Coarse SAND (SP), Trace Silt, Grades to Fine to Medium Sand to 19 Feet Then Fine to Coarse	SS									
	2356	100		2	SS									
	2355	63		3 Loose Gray-Brown Fine to Coarse SAND (SP) Little Fine Gravel, and Silt, Trace Clay	SS									
	6877	42		4	SS									
	611 1311	58		5	SS									
	6976	42		6 Medium Dense Fine to Coarse SAND (SP), Trace to Little Fine Gravel and Silt	SS									
	6976	71		7 3" Gray Silty CLAY Layer at 26'	SS									
734.2	3466	67		8 Very Stiff Gray Silty CLAY (CL), Trace Medium to Coarse Sand, Trace to Little Fine Sand, Grades to Clayey Silty CLAY (CL/ML), Shale Fragments Present	SS									2.0- 2.75
731.7				End of Boring at 32 Feet Monitoring Well Set at 29.5 Feet PID = None Detected										

LOGGED BY SJC	DRILLING CONTR E & F
DATE 9/22/93 CHK'D BY DAP	CHAS. MARKGRAF

TEMPLATE ID: WLL

ID: WMA

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 6" RB WITH MUD	BORING NO. W3D
BORING LOCATION: NE 1/4 of NE 1/4 of Section 17, T 46 N, R 10 E/W		SHEET 1 OF 2
SAMPLING METHOD: 2" SPLIT SPOON, SHELBY TUBE (34.5 - 38 FT)		DRILLING START TIME: FINISH TIME:
WATER LEVEL: TIME: DATE:		DATE: 4/8/93 DATE: 5/25/93
NORTHING 2115187.6 EASTING 1051022.7	DATUM ELEVATION 763.7	CASING DEPTH
DRILL RIG CME750 ATV/Track Rig	SURFACE CONDITIONS MARSH/WETLAND WET	
ANGLE Vertical BEARING -----	SAMPLE HAMMER TORQUE FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOBS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOBS/FOOT ON CASING	TEST RESULTS							
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS			
<div style="display: flex; flex-direction: column; align-items: center;"> <div style="margin-bottom: 10px;">▼</div> <div style="margin-bottom: 10px;">5</div> <div style="margin-bottom: 10px;">10</div> <div style="margin-bottom: 10px;">15</div> <div style="margin-bottom: 10px;">20</div> <div style="margin-bottom: 10px;">25</div> <div style="margin-bottom: 10px;">30</div> <div style="margin-bottom: 10px;">35</div> </div>				<p>Blind Drill to 34.5 Feet See Logs W3SA and W3SB for Geologic Descriptions of Upper 35 Feet</p>											
734.2			[Hatched Box]	1 Gray Silty CLAY (CL)											
729.2	-	17	1	Shelby Tube 34.5 to 36.5, Pushed Rocks and Gravel in End of Tube (Tube Destroyed)	SS										
	-	0	2		SS										

LOGGED BY SJC	DRILLING CONTR E & F, ETI
DATE 9/22/93 CHK'D BY DAP	CM/JR ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W4S
		SHEET 1 OF 1
	SAMPLING METHOD: 2" OD SPLIT SPOON	DRILLING START TIME FINISH TIME
BORING LOCATION: NW 1/4 of NE 1/4 of Section 17, T 46 N, R 10 E/W	WATER LEVEL TIME DATE	DATE DATE
NORTHING 2115202.0 EASTING 1050628.3	DATUM ELEVATION 767.5	CASING DEPTH 5/25/93 5/26/93
DRILL RIG CME 850	SURFACE CONDITIONS ASPHALT SURFACE/STOCK YARD	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOHS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOHS/FOOT ON CASING	TEST RESULTS									
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS					
765.5	2 2 2 2	15		Asphalt Surface Over FILL													
763.5	1 2 2 2	0		FILL: Brown Silty Fine to Coarse Gravel and Sand Brown Silty Clay and Trace Sand, Probable Fill	SS												
759.5	2 9 9 10	20		Black Clayey PEAT (PT)	SS												
10	5 10 10 9	50		Trace to Some Fine to Coarse Gravel Gray Fine to Coarse Silty SAND and GRAVEL (SP/GP) Trace Clay	SS												
15	5 7 7 11	50		PID = None Detected	SS												
15	11 17 30 50/3"	50		PID = None Detected	SS												
751.5	-	50		End of Boring at 16 Feet Well Set at to 15 Feet PID = None Detected													
20																	
25																	
30																	
35																	

LOGGED BY PMS	DRILLING CONTR ETI (for E & F)
DATE 9/17/93 CHK'D BY DAP	JOEL RUDA
	ID: WM1

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W55
		SHEET 1 OF 1
	SAMPLING METHOD: 5' CME SAMPLING TUBE 2" OD SPLIT SPOON (14 - 16 FT)	DRILLING START TIME FINISH TIME DATE DATE
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W NORTHING 2115375.1 EASTING 1050760.5 DATUM ELEVATION 771.1	WATER LEVEL TIME DATE	4/21/93 4/21/93
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED LANDFILL AREA, DRY	
ANGLE Vertical BEARING -----		
SAMPLE HAMMER TORQUE FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS
770.1 767.1 5 765.1 764.6	-	54		1 Brown Clayey Top Soil Over 4" Brown and Black Organic Clay Possible Peat (OH), Roots Present, Possible Fill Clayey Fine to Medium SAND (SC), Wood Fragments Over Fine to Coarse Sand, Trace to Little Fine Gravel Possible FILL	SB						.75	
765.1 764.6	-	50		2 Black Silty Organic SAND (SM), Some Gravel, Little Clay Wet Fine to Coarse Sand Layer	SB				63	NP	-	
10	-	57		3 Wet SAND (SM) Little Fine Gravel, Some Silt, Trace Gravel Grades to Fine to Coarse Sand 1/4" Silt Lens at Approximately 11.5"	SB						-	
15 755.1	7 10 9 9	92		4 Fine to Medium SAND (SM) Trace to Little Gravel Grades to Fine to Coarse Sand, Little Coarse Gravel	SS						-	
20 25 30 35				End of Boring at 16 Feet Monitoring Well Set at 15.51 Feet PID = None Detected								

LOGGED BY SJC	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
CHAS. MARKGRAF	
ID: WM1	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W6S
		SHEET 1 OF 1
	SAMPLING METHOD: 5' CME SAMPLING TUBE 2" OD SPLIT SPOON 14 - 16 FT	DRILLING START TIME FINISH TIME
BORING LOCATION: SE 1/4 of SE 1/4 of Section 8 , T 46 N, R 10 E/W	WATER LEVEL	DATE DATE
NORTHING 2115399.4 EASTING 1051541.1	TIME	4/16/93 4/16/93
DATUM ELEVATION 764.9	DATE	
DRILL RIG CME 750 ATV	CASING DEPTH	
ANGLE Vertical BEARING -----	SURFACE CONDITIONS	LOW LYING GRASS COVERED, TREED AREA
SAMPLE HAMMER TORQUE FT-LBS		

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS							
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS			
		38	[Symbol]	1 Black PEAT (PT)	SB										
5	759.9			2 1" Moist Greenish Organic Silty Clay Lens, Grades to 2" Light Tan-Gray Silty to Fine Sand Layer over Fine to Medium SAND (SM), Little Silt, Trace Clay	SB										
10		73		3 Grades Little Coarser Sand (1/4" Gray Clayey Silt Lense at 12")	SB										
15	750.5 749.5 749.0	96	[Symbol]	4 Stiff Greenish Gray Fat CLAY (CH), Trace Fine to Coarse Sand, Little to Some Silt SAND (SP)	SS										1.5
				End of Boring at 16 Feet Monitoring Well Set at 15 Ft PID = None Detected											

LOGGED BY <u>SJC</u>	DRILLING CONTR <u>E & F</u>
DATE <u>9/17/93</u>	CHK'D BY <u>DAP</u>
	CHAS MARKGRAF

SOIL BOREHOLE LOG

SITE NAME AND LOCATION H.O.D. Landfill - Antioch, Illinois	DRILLING METHOD: 4 1/4" ID HSA	BORING NO. W7D
BORING LOCATION: SW 1/4 of SW 1/4 of Section 9 , T 46 N, R 10 E/W		SHEET 1 OF 3
SAMPLING METHOD: 5' CME SAMPLE TUBE (0 - 94 FT) 2" OD SPLIT SPOON (94 - 100 FT) SHELBY TUBE (29 - 31 FT)		DRILLING START TIME: 4/13/93 FINISH TIME: 4/13/93
NORTHING 2116326.0	EASTING 1053153.3	DATE: 4/13/93
DATUM	ELEVATION 780.2	CASING DEPTH
DRILL RIG CME 750 ATV	SURFACE CONDITIONS GRASS COVERED PRAIRIE	
ANGLE Vertical	BEARING -----	
SAMPLE HAMMER TORQUE	FT-LBS	

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS
779.2	-	92		1 Approximately 6 - 12" Black Top Soil, Organic Silt Tan Laminated Silt (ML) With Limonite Precipitate, Grades to More Grayish with Laminated Limonite	SB				33	14		3.0- 1.25
775.2	-	97		2 Gray Laminated Silty CLAY to Clayey SILT (CL/ML) Interbedded with Tan Silt Gray Lean Clay (CL), Little to Some Silt	SB							3.0- 1.25
10	-	98		3 Gray Lean CLAY (CL) with Little to Some Silt, with Laminated Lenses of Silt, Little to Some Fine to Coarse Sand	SB							2.25- 1.25
15	-	97		4 Gray Lean CLAY (CL) Little to Some Silt, Sand Pocket with Coarse Gravel at 15 Feet, Trace to Little Fine to Coarse Sand, and Fine Gravel, Shale Fragments Present	SB							2.5- 3.25
20	-	97		5 Gray Massive Lean CLAY (CL), Trace to Little Silt and Trace Fine to Coarse Sand, Trace Fine to Coarse Gravel, Shale Fragments Approximately 6" Sandy Zone at 20 Ft	SB							2 1
25	-	85		6	SB				34	15		2.5- 3.0
30	-	92		7 Shelby Tube to 31' Collected CME Tube Sample 29' to 34'	SB							1.5- 2.5
35	-	97		8 Trace Shale Fragments	SB							2.5- 3.0
	-	97		9	SB							2.0-

LOGGED BY SJC	DRILLING CONTR E & F
DATE 9/17/93	CHK'D BY DAP
CHAS. MARKGRAF	
ID: WM1	

SOIL BOREHOLE LOG

SITE NAME AND LOCATION **H.O.D. Landfill - Antioch,**
Illinois

SHEET
3 OF 3

BORING NO.
W7D

DEPTH IN FEET (ELEVATION)	BLOWS/6 IN. ON SAMPLER	RECOVERY %	SYMBOL	SAMPLE NUMBER AND DESCRIPTION OF MATERIALS	SAMPLER AND BIT	CASING TYPE	BLOWS/FOOT ON CASING	TEST RESULTS				
								WATER CONTENT %	LIQUID LIMIT %	PLASTIC LIMIT %	SPECIFIC GRAVITY	OTHER TESTS
<div style="display: flex; flex-direction: column; align-items: center;"> <div style="margin-bottom: 10px;">680.2</div> <div style="margin-bottom: 10px;">100</div> <div style="margin-bottom: 10px;">105</div> <div style="margin-bottom: 10px;">110</div> <div style="margin-bottom: 10px;">115</div> <div style="margin-bottom: 10px;">120</div> <div style="margin-bottom: 10px;">125</div> <div style="margin-bottom: 10px;">130</div> <div style="margin-bottom: 10px;">135</div> <div style="margin-bottom: 10px;">140</div> <div style="margin-bottom: 10px;">145</div> <div style="margin-bottom: 10px;">150</div> </div>	8 10 16 20	75	22	More Fine, Trace to Little Fine Gravel Medium Dense Fine to Medium SAND (SP), Little Coarse Sand, Trace to Little Fine Gravel End of Boring at 100 Feet Monitoring Well Set at 99.94 Feet PID = None Detected	SS						-	

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115185.3 N
1051029.2E

Elevation Ground Level: 763.8
Top of Casing 766.54

4.00

5.30

Drilling Summary:

Total Depth 16'
 Borehole Diameter 8.5 in.
 Casing Stick-up Height: 2.74 in.
 Driller Charles Markgraf
Environmental and Foundation Drilling
Inc. (E & F)
 Rig CME750 ATV
 Bit(s) 4.25 in. ID X 8.5 in. OD HSA

Drilling Fluid None

Protective Casing Aluminum WMX Spec.- 5ft

Well Design & Specifications

Basis: Geologic Log Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
<u>-2.74 - 5.3</u>	<u>C1</u>	<u>766.54-758.5</u>
<u>5.3 - 15.64</u>	<u>S1</u>	<u>758.5-748.16</u>

Casing: C1 2 in. ID Schedule 40 PVC flush Thread
 C2 _____

Screen: S1 2 in. ID Schedule 40 PVC, .010 Slot Size
 S2 _____

Filter Pack: #45-55 Red flint sand (5-15.64 ft) fine silica sand (4.0-5ft)

Grout Seal: None

Bentonite Seal: Bentonite Chips (0-4feet)


Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	<u>4/7</u>		<u>4/7</u>	
Geophys. Logging:				
Casing:				
Filter Placement:	<u>4/7</u>		<u>4/7</u>	
Cementing:				
Development:	<u>5/5</u>		<u>5/5</u>	

Well Development:
Surged and purged with stainless steel bailer and nylon rope. Purged 24 gallons, one well volume = 2.4 gallons

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)



Comments: _____

SITE NAME: Bob Landfill
 LOCAL: Antioch, Ill.
 WC
 SUPERVISOR: S. Chilton - Arzys

SJC/llr/DAP

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115189.4N
1051027.8E

Elevation Ground Level 763.7
Top of Casing 766.81

Drilling Summary:

Total Depth 32 ft.
Borehole Diameter 8.5 in.
Casing Stick-up Height: 3.11 ft
Driller Charles Markgraf
Environmental & Foundation Drilling
Inc. (E & F)
Rig CME750 ATV
Bit(s) 4 1/2 in. ID X 8 1/2 in. OD HSA
Drilling Fluid None
Protective Casing Alum. WMX Spec. - 5ft

Well Design & Specifications

Basis: Geologic Log X Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
-3.11 - 24.55	C1	766.81 - 739.15
24.55 - 29.57	S1	739.15 - 734.13

Casing: C1 2 in. ID Schedule 40 PVC flush thread
C2

Screen: S1 2 in. ID Schedule 40 PVC .010 Slot Size
S2

Filter Pack: #45-55 Red flint sand
(22.55 - 29.57 ft)

Grout Seal: Bentonite Slurry
(8.5 - 17.55 ft)

Bentonite Seal: Bentonite Chips
(17.55 - 22.55 ft), (0 - 8.5ft)

Comments: 18" pipe wrench dropped into annular space

SJC/11r/DAP

Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993			
	4/7		4/7	
Geophys. Logging:				
Casing:				
Filter Placement:	4/7		4/7	
Cementing:				
Development:	5/5		5/5	


Well Development:

Surged & Purged w/PVC bailer and steel cable. Purged 200 gallons, one well volume = 4.7 gallons

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)

Recovery Data:



8.50

17.55

22.55

24.55

29.57

SITE NAME HOD Landfill
LOCATION Antioch, Ill.
WC
SUPERVISOR S. Chilton - Wazyn, Inc.

0.00

Well No. W32
Boring No. X-Ref: W12

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115137.6 N
1051022.7 E

Elevation Ground Level 763.73
Top of Casing 765.93

Drilling Summary:

Total Depth 80 ft.
 Borehole Diameter 8.5 in.
 Casing Stick-up Height: 2.2 ft.
 Driller Charles Markgraf E & F
Joel Ruda, ETI

Rig CME750 ATV
 Bit(s) 8in. - 6in. roller bit rotary
wash
 Drilling Fluid 50 lbs supergel X/100
gallon H2O
 Protective Casing Steel Well Box

Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993			
	4/28		5/15	
Geophys. Logging:				
Casing:				
Filter Placement:	5/25		5/25	
Cementing:				
Development:	5/27		5/27	

Well Design & Specifications
 Basis: Geologic Log Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
0 - 34	C1	763.73 - 729.73
-2.2 - 73.3	C2	765.93 - 690.43
73.3 - 78	S1	690.43 - 685.73

Well Development:
Surged and Purged w/PVC bailers
and steel cable, Purged 200
gallon, one well volume - 8 gals


Casing: C1 6in. ID Schedule 40 PVC,
flush threaded
 C2 2in. ID Schedule 40 PVC,
flush threaded
 Screen: S1 2in. ID Schedule 40 PVC,
.010 Slot Size
 S2 _____

Filter Pack: #45-55 Red flint sand
(70.9 - 78 ft.)

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)

Grout Seal: 40 lb supergel/85 gallon
H2O (0-65 ft)



Bentonite Seal: Bentonite Chips (65-70.9)

Comments: _____

SJC/llr/DAP

65.00

70.90

73.30

78.00

SITE NAME: HOD Landfill
LOCALITY: Antioch, Ill.

WC

Warzyn

SUPERVISED BY: S. Chilton

CONFORM

0.00

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115202N
1050628.3 E

Elevation Ground Level 767.5
Top of Casing 769.97

Drilling Summary:

Total Depth 16'
Borehole Diameter 8.5 in.
Casing Stick-up Height: 2.47 ft
Driller Joel Ruda
Exploration Technolgy Inc. (ETI)
for (E & F)
Rig CME850
Bit(s) 4 1/2 in. ID X 8.5 in. OD HSA
Drilling Fluid None
Protective Casing Alum. WMX Spec.

Well Design & Specifications

Basis: Geologic Log X Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
-2.47	C1	769.97 - 762.5
5	S1	762.5 - 752.5

Casing: C1 2 in. ID Schedule 40 PVC flush threaded

C2

Screen: S1 2 in. ID Schedule 40 PVC .010 Slot Size

S2

Filter Pack: Red flint sand (4 - 15 ft)

Grout Seal: None

Bentonite Seal: Hydrated Granular Bentonite (0 - 4 ft)

Comments: Pulled augers and redrilled w/wooden plug

Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993		5/26	
Geophys. Logging:				
Casing:				
Filter Placement:	5/26		5/26	
Cementing:				
Development:	6/1		6/1	


Well Development:

Surged & Purged with PVC bailer and steel cable. Purged 20 gals. one well volume = 1.5 gallons

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)

Recovery Data:



SJC/11r/DAP

4.00

5.00

15.00

SITE NAME: HOD Landfill
LOCATION: Antioch, Ill.
WC
SUPERVISED BY: S. Chittison - Marzynn

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115375.1 N Elevation Ground Level 771.10 ft MSL
1050760.5 E Top of Casing 773.49

Drilling Summary:

Total Depth 16'
 Borehole Diameter 8.5'
 Casing Stick-up Height: 2.39'
 Driller Charles Markgraf
Environmental & Foundation Drilling Inc.
 (E & F)
 Rig CME 750 ATV
 Bit(s) 4 1/4" ID x 8.5" IDHSA
 Drilling Fluid None
 Protective Casing Alum WMX Spec. 5.5 ft

Well Design & Specifications

Basis: Geologic Log X Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
-2.39 - 5.22	C1	773.49 - 765.88
5.22 - 15.51	S1	768.88 - 755.59

Casing: C1 2in ID Schedule 40 PVC flush Thread

C2

Screen: S1 2" Schedule 40 PVC, 010 in. Slot size

S2

Filter Pack: 45-55 Redflint filter sand (3.9 - 15.51 ft)

Grout Seal: None

Bentonite Seal: Hydrated Granular Bentonite (0 - 3.9 ft)

Comments: Alconox solution was used for pre decon, of development equipment.

Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993			
	4/21		4/21	
Geophys. Logging:				
Casing:				
Filter Placement:	4/21		4/21	
Cementing:				
Development:	5/4		5/4	


Well Development:

Surged & purged w/PVC Bailer & nylon rope. Purged 59.4 gallons, one well volume = 1.1 gallons

Stabilizaton Test Data:

Time	pH	Spec. Cond.	Temp (C)

Recovery Data:



SITE NAME: 110D Landfill
 LOCATION: Antioch, Ill.
 SUPERVISOR: S. Chiltonson - Urzym Inc.

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2115399.4 N Elevation Ground Level 764.9
1051541.1 E Top of Casing 767.41

Drilling Summary:

Total Depth 16'
 Borehole Diameter 8.5 in.
 Casing Stick-up Height: 2.5'
 Driller Charles Markgraf
Environmental & Foundation Drilling,
Inc. (E & F)
 Rig CME750 ATV
 Bit(s) 4 1/2 in. ID X 8.5 in OD HSA

Drilling Fluid None

Protective Casing Aluminum WMX Spec.

Well Design & Specifications

Basis: Geologic Log Geophysical Log

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
-2.51 - 5.02	C1	767.41 - 759.88
5.02 - 15	S1	759.88 - 749.9

Casing: C1 2 in. ID Schedule 40 PVC
flush thread
 C2 _____

Screen: S1 2 in. ID Schedule 40 PVC .010"
Slot Size
 S2 _____

Filter Pack: #45-55 Red flint sand
(4 - 15 ft)

Grout Seal: _____

Bentonite Seal: Hydrated Bentonite Chips and
Granular (0 - 4 ft)

Comments: _____


Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993			
	4/16		4/16	
Geophys. Logging:				
Casing:				
Filter Placement:	4/16		4/16	
Cementing:				
Development:	5/4		5/4	

Well Development:
 Surged & purged w/stainless steel bailer and steel cable
 purged 75 gallons, one volume = 2.1 gallons

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)



SJC/TF/DAF

0.00

4.00

5.00

15.00

SHE NAME HOD Landfill
 LOCATION Antioch, Ill.
 WC
 SUPERVISED BY S. Chiltonson - Warzyn Inc.

MONITOR WELL CONSTRUCTION SUMMARY

Survey Coords: 2116326 N
1053153.3 E

Elevation Ground Level 730.2
 Top of Casing 782.87

Drilling Summary:

Total Depth 100 ft
 Borehole Diameter 8.5 in.
 Casing Stick-up Height: 2.67 ft
 Driller Charles Markgraf E & F

Rig CME750 ATV
 Bit(s) 4 1/2 in. ID X 8 1/2 in. OD HSA

Drilling Fluid Water

Protective Casing Alum. WMX Spec. - 7ft

Well Design & Specifications

Basis: Geologic Log X Geophysical Log _____

Casing String (s): C=Casing S=Screen.

Depth	String(s)	Elevation
-2.67 - 94.92	C1	782.87 - 685.28
94.92 - 99.94	S1	685.28 - 680.26

Casing: C1 2 in. ID Schedule 40 PVC,
flush threaded

C2 _____

Screen: S1 2 in. ID Schedule 40 PVC,
.010 Slot Size

S2 _____

Filter Pack: #45-55 Red flint sand
(93-99.94 ft)

Grout Seal: Bentonite slurry
(0-90 ft)

Bentonite Seal: Bentonite Chips (90-93 ft)

Comments: _____

Construction Time Log:

Task	Start		Finish	
	Date	Time	Date	Time
Drilling	1993			
	4/14		4/14	
Geophys. Logging:				
Casing:				
Filter Placement:	4/14		4/14	
Cementing:				
Development:	5/5		4/14	


Well Development:

Surged & purged for 30 min. with
PVC bailer and cable. Purged
100 gallons with keck pump.
one well volume = 8.29 gallons

Stabilization Test Data:

Time	pH	Spec. Cond.	Temp (C)

Recovery Data:



SHE NAME: IOD Landfill
 IODCA Antioch, Ill.

WC

Arzyu, Inc.

SUPERVISED BY: S. Chiltonson

90.00
 93.00
 94.92
 99.94

SJC/ILF/DAP

CONS-11

I

MONITORING WELL
DEVELOPMENT DATA

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-6-93 Page 1 of 1
 Project Number 10010201 Well Number W2D
 Diameter of Well 2 inches Length of Water Column 48.6 ft
 Depth of Well 90.35 ft One Well Volume 7.97 gallons
 Initial Water Level 41.75 ft Time 9:28
 Field Personnel Steven Chillson, Terese Burke
 Development Method PVC Bailer & Stainless Steel Cable/Keck Pump

WITHDRAWAL OF WELL VOLUMES

	Volume No. 1	Volume No. 52.5	Volume No.	Volume No.	Volume No.
Time End					
Flushing	10:00	17:30			
Volume Flushed	3 gals	420 gals			
Temperature	--	--			
Conductivity	--	--			
pH	--	--			
Odor	None	None			
Turbidity	Turbid	Clear			
Color	Gr Brown	Clear			
Other	--	--			
	Volume No.	Volume No.	Volume No.	Volume No.	Volume No.
Time End					
Flushing					
Volume Flushed					
Temperature					
Conductivity					
pH					
Odor					
Turbidity					
Color					
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

Purged and surged 3 gallons at 10:00,
 10:30 Pumping rate at approximately
 1 gal/minute for 420 minutes
 Total Volume Flushed = 423 gallons

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-5-93 Page 1 of 1
 Project Number 10010201 Well Number W3SA
 Diameter of Well 2 inches Length of Water Column 14.25 ft
 Depth of Well 17.65 ft One Well Volume 2.4 gallons
 Initial Water Level 3.4 ft Time 15:24
 Field Personnel Terese Burke, Steven Chillson
 Development Method SS Bailer & Nylon Rope

WITHDRAWAL OF WELL VOLUMES

	Volume No. 2	Volume No. 4	Volume No. 6	Volume No. 8	Volume No. 10
Time End					
Flushing	16:12	16:19	16:30	16:37	16:46
Volume Flushed	4.8 gals	4.8 gals	4.8 gals	4.8 gals	4.8 gals
Temperature		10 ^o c	9 ^o c	9 ^o c	9 ^o c
Conductivity		600	650	700	700
pH		7.11	7.19	7.17	7.19
Odor	None	None	None	None	None
Turbidity	Turbid	Turbid	Turbid	Turbid	Turbid
Color	Brown	Brown	Brown	Brown	Brown
Other					
	Volume No.	Volume No.	Volume No.	Volume No.	Volume No.
Time End					
Flushing					
Volume Flushed					
Temperature					
Conductivity					
pH					
Odor					
Turbidity					
Color					
Other					

WELL CASING VOLUMES

GAL/FT 1-1/4" = 0.077
 1-1/2" = 0.10
 2" = 0.164
 2-1/2" = 0.24
 3" = 0.37
 3-1/2" = 0.50
 4" = 0.65
 6" = 1.46

Remarks:

Surged and purged for 30 minutes
 15:35-16:05 purged 5 gallons
 Total volume flushed = 24 gallons

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-5-93 Page 1 of 1
 Project Number 10010201 Well Number W3SB
 Diameter of Well 2 inches Length of Water Column 28.9 ft
 Depth of Well 32.6 ft One Well Volume 4.7 gallons
 Initial Water Level 3.7 ft Time 15:26
 Field Personnel Steven Chillson, Clayton Heffter
 Development Method PVC Bailer, Steel Cable

WITHDRAWAL OF WELL VOLUMES

	Volume No. 4	Volume No. 8	Volume No. 12	Volume No. 16	Volume No. 20
Time End					
Flushing	16:18	16:30	16:45	17:00	17:14
Volume Flushed	20 gals				
Temperature	10 ^o c				
Conductivity	1000	1000	1000	1000	1000
pH	7.06	7.17	7.19	7.17	7.16
Odor	None	None	None	None	None
Turbidity	Turbid	Turbid	Turbid	Sl Turbid	Sl Turbid
Color	Brown	Brown	Brown	Brown	Brown
Other					
	Volume No. 24	Volume No. 28	Volume No. 32	Volume No. 36	Volume No. 40
Time End					
Flushing	17:25	17:36	17:48	18:00	18:26
Volume Flushed	20 gals				
Temperature	10 ^o c				
Conductivity	1000	1000	1000	1000	1000
pH	7.14	7.14	7.14	7.06	7.04
Odor	None	None	None	None	None
Turbidity	Sl Turbid				
Color	Gray-Br	Gray-Br	Gray-Br	Gray-Br	Gray-Br
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

Surged and purged for 30 minutes
 prior to withdraw of well volumes
 Total volume flushed = 200 gallons

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5/27/93 Page 1 of 1
 Project Number 10010201 Well Number W3D
 Diameter of Well 2 inches Length of Water Column 47.97
 Depth of Well 80.60 TOIC One Well Volume 7.9 gallons
 Initial Water Level 32.63 Time 12:30
 Field Personnel David A. Pieczynski
 Development Method PVC Bailer & Cable

WITHDRAWAL OF WELL VOLUMES

	<u>Volume No. 2.5</u>	<u>Volume No. 5</u>	<u>Volume No. 7.5</u>	<u>Volume No. 10</u>	<u>Volume No. 12.5</u>
Time End Flushing	<u>13:15</u>	<u>13:45</u>	<u>14:15</u>	<u>14:45</u>	<u>15:15</u>
Volume Flushed	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>
Temperature	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Conductivity	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
pH	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Odor	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>
Turbidity	<u>Mod Turbid</u>	<u>Sl Turbid</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>
Color	<u>Lt Gray Br</u>	<u>Gray/Brn</u>	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>
Other	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
	<u>Volume No. 15</u>	<u>Volume No. 17.5</u>	<u>Volume No. 20</u>	<u>Volume No. 22.5</u>	<u>Volume No. 25</u>
Time End Flushing	<u>16:00</u>	<u>16:30</u>	<u>17:00</u>	<u>17:30</u>	<u>18:00</u>
Volume Flushed	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>	<u>20 gals</u>
Temperature	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Conductivity	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
pH	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Odor	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>
Turbidity	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>	<u>Clear</u>
Color	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>	<u>Lt Gray Br</u>
Other	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>

WELL CASING VOLUMES

GAL/FT 1-1/4" = 0.077
 1-1/2" = 0.10
 2" = 0.164
 2-1/2" = 0.24
 3" = 0.37
 3-1/2" = 0.50
 4" = 0.65
 6" = 1.46

Remarks:

Surged & purged 1/2 hour
 Removed 5 gals - gray, turbid, no odor
 Bailed 200 gallons
 Well volume = 7.9 gallons
 Total Volume Flushed = 200 gallons

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5/27/93 Page 1 of 1
 Project Number 10010201 Well Number W4S
 Diameter of Well 2 inches Length of Water Column 8.78
 Depth of Well 16.75 One Well Volume Approx. 1.4 gals
 Initial Water Level 7.97 Time 10:05 a.m.
 Field Personnel David A. Pieczynski
 Development Method PVC Bailer & Cable

WITHDRAWAL OF WELL VOLUMES

	<u>Volume No. 1</u>	<u>Volume No. 2</u>	<u>Volume No. 3</u>	<u>Volume No. 4</u>	<u>Volume No. 5</u>
Time End Flushing	<u>10:40</u>	<u>10:45</u>	<u>10:50</u>	<u>10:55</u>	<u>11:00</u>
Volume Flushed	<u>2 gals</u>				
Temperature	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Conductivity	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
pH	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Odor	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>
Turbidity	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>
Color	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>
Other					
	<u>Volume No. 6</u>	<u>Volume No. 7</u>	<u>Volume No. 8</u>	<u>Volume No. 9</u>	<u>Volume No. 10</u>
Time End Flushing	<u>11:05</u>	<u>11:10</u>	<u>11:15</u>	<u>11:20</u>	<u>11:25</u>
Volume Flushed	<u>2 gals</u>				
Temperature	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Conductivity	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
pH	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>	<u>--</u>
Odor	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>	<u>None</u>
Turbidity	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>	<u>Turbid</u>
Color	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>	<u>Gray/Brn</u>
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

Surge & purge for 1/2 half hour
 Water dark gray brown, turbid - pulled
 approximately 7 gallons during surge
 and purge
 Purged total of 27 gallons

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-4-93 Page 1 of 2
 Project Number 10010201 Well Number W5S
 Diameter of Well 2 inches Length of Water Column 7.0 ft
 Depth of Well 17.5 ft One Well Volume 1.1 gallons
 Initial Water Level 10.5 ft Time 13:21
 Field Personnel Terese Burke
 Development Method PVC Bailer and Nylon Rope

WITHDRAWAL OF WELL VOLUMES

	Volume No. 4.5	Volume No. 9	Volume No. 13.5	Volume No. 18	Volume No. 22.5
Time End Flushing	14:08	14:16	14:25	14:31	14:46
Volume Flushed	5 gals	5 gals	5 gals	5 gals	5 gals
Temperature	--	--	--	--	--
Conductivity	--	--	--	--	--
pH	--	--	--	--	--
Odor	None	None	None	None	None
Turbidity	Turbid	Turbid	Turbid	Turbid	Turbid
Color	Brown	Brown	Brown	Brown	Brown
Other					
	Volume No. 27	Volume No. 31.5	Volume No. 36	Volume No. 40.5	Volume No. 45
Time End Flushing	14:53	15:00	15:09	15:17	15:25
Volume Flushed	5 gals	5 gals	5 gals	5 gals	5 gals
Temperature	--	--	--	--	--
Conductivity	--	--	--	--	--
pH	--	--	--	--	--
Odor	None	None	None	None	None
Turbidity	Turbid	Turbid	Turbid	Turbid	Turbid
Color	Brown	Brown	Brown	Brown	Brown
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

See Page 2 of 2

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-4-93 Page 2 of 2
 Project Number 10010201 Well Number W55
 Diameter of Well 2 inches Length of Water Column 7.0 ft
 Depth of Well 17.5 ft One Well Volume 1.1 gallons
 Initial Water Level 10.5 ft Time 13:21
 Field Personnel Terese Burke
 Development Method PCB Bailer & Nylon Rope

WITHDRAWAL OF WELL VOLUMES

	<u>Volume No. 45</u>	<u>Volume No. 49.5</u>	<u>Volume No. 54</u>	<u>Volume No.</u>	<u>Volume No.</u>
Time End					
Flushing	<u>15:48</u>	<u>15:55</u>	<u>16:10</u>		
Volume Flushed	<u>5 gals</u>	<u>5 gals</u>	<u>5 gals</u>		
Temperature	<u>--</u>	<u>--</u>	<u>--</u>		
Conductivity	<u>--</u>	<u>--</u>	<u>--</u>		
pH	<u>--</u>	<u>--</u>	<u>--</u>		
Odor	<u>None</u>	<u>None</u>	<u>None</u>		
Turbidity	<u>SI Turbid</u>	<u>SI Turbid</u>	<u>SI Turbid</u>		
Color	<u>Brown</u>	<u>Brown</u>	<u>Brown</u>		
Other					
	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>
Time End					
Flushing					
Volume Flushed					
Temperature					
Conductivity					
pH					
Odor					
Turbidity					
Color					
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

Total Volume Flushed = 65 gallons
 Initially surged and purged for
 30 minutes, removing 10 gallons of
 water
 Alconox used to decon development
 equipment

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-4-93 Page 1 of 1
 Project Number 10010201 Well Number W6S
 Diameter of Well 2 inches Length of Water Column 12.77 ft
 Depth of Well 17.09 ft One Well Volume 2.1 gallons
 Initial Water Level 4.32 ft Time 15:26
 Field Personnel Steve Chillson
 Development Method SS Bailer and Cable and PVC Bailer

WITHDRAWAL OF WELL VOLUMES

	<u>Volume No. 1</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>
Time End Flushing					
Volume Flushed	<u>75 gals</u>				
Temperature	<u>--</u>				
Conductivity	<u>--</u>				
pH	<u>--</u>				
Odor	<u>None</u>				
Turbidity	<u>--</u>				
Color	<u>--</u>				
Other					
	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>	<u>Volume No.</u>
Time End Flushing					
Volume Flushed					
Temperature					
Conductivity					
pH					
Odor					
Turbidity					
Color					
Other					

WELL CASING VOLUMES

GAL/FT	1-1/4"	=	0.077
	1-1/2"	=	0.10
	2"	=	0.164
	2-1/2"	=	0.24
	3"	=	0.37
	3-1/2"	=	0.50
	4"	=	0.65
	6"	=	1.46

Remarks:

37.5 volumes surged & purged

WELL DEVELOPMENT DATA SHEET

Project HOD Date 5-5-93 Page 1 of 1
 Project Number 10010201 Well Number W7D
 Diameter of Well 2 inches Length of Water Column 50.55 ft
 Depth of Well 102.25 ft One Well Volume 8.29 gallons
 Initial Water Level 51.7 ft Time 9:22
 Field Personnel Terese Burke, Steven Chillson
 Development Method PVC bailer & steel Cable/Keck pump

WITHDRAWAL OF WELL VOLUMES

	Volume No. 3	Volume No. 6	Volume No. 9	Volume No. 12	Volume No. 13
Time End Flushing	10:38	11:10	11:50	12:48	18:50
Volume Flushed	25 gals	25 gals	25 gals	25 gals	267 gals
Temperature	--	--	--	--	--
Conductivity	--	--	--	--	--
pH	--	--	--	--	--
Odor	--	--	--	--	--
Turbidity	Clear	Clear	Clear	Clear	Clear
Color	None	None	None	None	None
Other					
	Volume No.	Volume No.	Volume No.	Volume No.	Volume No.
Time End Flushing					
Volume Flushed					
Temperature					
Conductivity					
pH					
Odor					
Turbidity					
Color					
Other					

WELL CASING VOLUMES

GAL/FT 1-1/4" = 0.077
 1-1/2" = 0.10
 2" = 0.164
 2-1/2" = 0.24
 3" = 0.37
 3-1/2" = 0.50
 4" = 0.65
 6" = 1.46

Remarks:


Surged and purged for 30 minutes
 and removed 4 gallons of water
 Water slightly turbid and brown gray
 very little silt.
 Keck pump rate = .7 gallons/minute for
 382 minutes starting at 12:50
 Total Volume removed = 371 gallons

J

RESULTS OF IN-FIELD
HYDRAULIC CONDUCTIVITY TESTING

0.0033	3.22	2.7193	0.50072	1
0.0066	3.03	2.7127	0.31729	1
0.0099	2.85	2.7062	0.14385	1
0.0133	2.8	2.6994	0.10058	1
0.0166	2.78	2.6929	0.087106	1
0.0233	2.74	2.6797	0.060301	1
0.0266	2.72	2.6732	0.046776	1
0.03	2.71	2.6666	0.043431	1
0.0333	2.69	2.6601	0.029875	1
0.05	2.61	2.6278	-0.017755	1
0.0666	2.56	2.596	-0.035969	1
0.0833	2.52	2.5644	-0.04438	1
0.1	2.48	2.5332	-0.053175	1
0.1166	2.44	2.5025	-0.062533	1
0.1333	2.41	2.4721	-0.062081	1
0.15	2.37	2.442	-0.071999	1
0.1666	2.33	2.4125	-0.08246	1
0.1833	2.3	2.3831	-0.083104	1
0.2	2.27	2.3541	-0.084105	1
0.2166	2.24	2.3256	-0.085629	1
0.2333	2.2	2.2973	-0.09733	1
0.25	2.18	2.2694	-0.089374	1
0.2666	2.15	2.2419	-0.091924	1
0.2833	2.12	2.2146	-0.094642	1
0.3	2.09	2.1877	-0.097693	1
0.3166	2.07	2.1612	-0.091231	1
0.3333	2.04	2.1349	-0.094931	1
0.4167	1.91	2.0083	-0.098306	1
0.5	1.8	1.8893	-0.089329	1
0.5833	1.69	1.7774	-0.087401	1
0.6667	1.59	1.672	-0.081981	1
0.75	1.5	1.5729	-0.072929	1
0.8333	1.42	1.4797	-0.059746	1
0.9167	1.35	1.392	-0.04198	1
1	1.27	1.3095	-0.039516	1
1.0833	1.21	1.2319	-0.021937	1
1.1667	1.15	1.1589	-0.0088696	1
1.25	1.09	1.0902	-0.0002155	1
1.3333	1.04	1.0256	0.014371	1
1.4166	0.99	0.96487	0.025132	1
1.5	0.94	0.90764	0.032359	1
1.5833	0.91	0.85387	0.05613	1
1.6667	0.85	0.80323	0.046774	1
1.75	0.82	0.75564	0.064359	1
1.8333	0.77	0.71088	0.059125	1
1.9167	0.74	0.66871	0.071288	1
2	0.71	0.6291	0.080904	1
2.5	0.55	0.43603	0.11397	1
3	0.44	0.30222	0.13778	1
3.5	0.36	0.20947	0.15053	1
4	0.31	0.14519	0.16481	1
4.5	0.24	0.10063	0.13937	1
5	0.22	0.069749	0.15025	1
5.5	0.18	0.048344	0.13166	1
6	0.17	0.033507	0.13649	1
6.5	0.16	0.023224	0.13678	1
7	0.14	0.016097	0.1239	1
7.5	0.12	0.011157	0.10884	1
8	0.12	0.0077331	0.11227	1

HODUSIS




DATA SET
hodusis.dst
07/23/93

AQUIFER TYPE
Unconfined
SOLUTION METHOD
Bower-Price

ESTIMATED PARAMETERS
K = 0.0007109 ft/min
Y0 = 2.623 ft

TEST DATA:
MD = 3.22 ft
rc = 0.083 ft
rw = 0.42 ft
L = 5.7 ft
b = 7 ft
H = 10.6 ft

HODUSS3S




DATA SET
hoduss3s.dat
07/23/93

ADJUSTER TYPE
Unconfined
SOLUTION METHOD
Bower-Rice

ESTIMATED PARAMETERS
K = 0.04175 ft/min
Y0 = 2.95 ft

TEST DATA
H0 = 3.19 ft
rc = 0.083 ft
rw = 0.42 ft
L = 5.3 ft
b = 23 ft
H = 17.22 ft

HODUS3D



DATA SET

hodus3d.dat
07/23/93

AQUIFER TYPE

Unconfined

SOLUTION METHOD

Bouwer-Rice


ESTIMATED PARAMETERS

$K = 0.0003176$ ft/min
 $y_0 = 33.79$ ft

TEST DATA

$H_0 = 19.77$ ft
 $r_c = 0.083$ ft
 $r_w = 0.25$ ft
 $L = 5.3$ ft
 $b = 45$ ft
 $H = 46.3$ ft

HODUS4S



DATA SET

nodus4s.dat
07/03/93

AQUIFER TYPE

Unconfined

SOLUTION METHOD

Bower-Rice

ESTIMATED PARAMETERS

$K = 0.04533$ ft/min
 $y_0 = 1.169$ ft

TEST DATA:

$H_0 = 3.3$ ft
 $r_c = 0.083$ ft
 $r_w = 0.42$ ft
 $L = 5.7$ ft
 $b = 13$ ft
 $H = 14.05$ ft


HODUS6S

DATA SET
hodus6s.dat
07/23/93


AQUIFER TYPE
Unconfined
SOLUTION METHOD
Bouwer-Rice

ESTIMATED PARAMETERS
K = 0.1019 ft/min
Y0 = 2.532 ft

TEST DATA
H0 = 1.91 ft
rc = 0.083 ft
rw = 0.42 ft
L = 5.7 ft
b = 36 ft
H = 37.31 ft



HODUS6D



DATA SET

nodus6d.dat
07/23/93

AQUIFER TYPE

Unconfined

SOLUTION METHOD

Bowyer-Rice


ESTIMATED PARAMETERS

K = 0.002144 ft/min
Y0 = 22.13 ft

TEST DATA:

H0 = 19.14 ft
rC = 0.083 ft
rw = 0.33 ft
L = 5.7 ft
b = 9.17 ft
H = 45.64 ft

HODW3SB



DATA SET:

a hcdw3sb.dat

07/29/93

AQUIFER TYPE

Unconfined

SOLUTION METHOD

Bouwer-Rice

ESTIMATED PARAMETERS:

$K = 0.1405$ ft/min

$y0 = 7.557$ ft

TEST DATA:

$H0 = 6.02$ ft

$rc = 0.083$ ft

$rw = 0.33$ ft


$L = 4.3$ ft

$b = 27.85$ ft

$H = 27.85$ ft

0.02	8.91	8.7156	0.19444	1
0.0233	8.85	8.7047	0.1453	1
0.0266	8.85	8.6939	0.15614	1
0.03	8.76	8.6827	0.0773	1
0.0333	8.74	8.6719	0.068118	1
0.05	8.6	8.6173	-0.017343	1
0.0666	8.53	8.5635	-0.033471	1
0.0833	8.46	8.5096	-0.049614	1
0.1	8.42	8.4561	-0.036096	1
0.1166	8.36	8.4032	-0.043231	1
0.1333	8.3	8.3504	-0.050382	1
0.15	8.25	8.2979	-0.047865	1
0.1666	8.19	8.246	-0.05599	1
0.1833	8.14	8.1941	-0.05413	1
0.2	8.14	8.1426	-0.0025958	1
0.2166	8.01	8.0917	-0.081691	1
0.2333	7.92	8.0408	-0.1208	1
0.25	7.95	7.9902	-0.040232	1
0.2666	7.89	7.9403	-0.05028	1
0.2833	7.84	7.8903	-0.050342	1
0.3	7.78	7.8407	-0.060719	1
0.3166	7.75	7.7917	-0.041702	1
0.3333	7.71	7.7427	-0.032698	1
0.4167	7.45	7.5025	-0.05255	1
0.5	7.22	7.2701	-0.050125	1
0.5833	7	7.0449	-0.0449	1
0.6667	6.83	6.8264	0.0036055	1
0.75	6.62	6.6149	0.0050838	1
0.8333	6.42	6.41	0.010011	1
0.9167	6.25	6.2112	0.038824	1
1	6.07	6.0188	0.051243	1
1.0833	5.85	5.8323	0.017701	1
1.1667	5.66	5.6514	0.008596	1
1.25	5.5	5.4763	0.023674	1
1.3333	5.35	5.3067	0.043328	1
1.4166	5.16	5.1423	0.017726	1
1.5	5.03	4.9828	0.047219	1
1.5833	4.84	4.8284	0.011583	1
1.6667	4.73	4.6787	0.051342	1
1.75	4.59	4.5337	0.056284	1
1.8333	4.43	4.3933	0.036736	1
1.9167	4.34	4.257	0.082998	1
2	4.21	4.1251	0.084878	1
2.5	3.45	3.4151	0.034913	1
3	2.8	2.8273	-0.027266	1
3.5	2.35	2.3406	0.0093758	1
4	1.94	1.9377	0.0022548	1
4.5	1.51	1.6042	-0.094212	1
5	1.34	1.3281	0.011913	1
5.5	1.04	1.0995	-0.059491	1
6	0.89	0.91024	-0.020241	1
6.5	0.71	0.75357	-0.043566	1
7	0.56	0.62386	-0.063859	1
7.5	0.47	0.51648	-0.046478	1
8	0.31	0.42758	-0.11758	1
8.5	0.29	0.35398	-0.063982	1
9	0.26	0.29305	-0.033053	1
9.5	0.22	0.24261	-0.022611	1
10	0.14	0.20085	-0.060852	1

HODW3D



DATA SET

hodw3d 041
07/23/53

AQUIFER TYPE

Unconfined
SOLUTION METHOD:
Bower-Arice


ESTIMATED PARAMETERS

K = 0.000739 ft/min
Y0 = 8.782 ft

TEST DATA

H0 = 12.99 ft
rc = 0.083 ft
rw = 0.33 ft
L = 4.3 ft
b = 45 ft
H = 43.53 ft

HODW4S




DATA SET
HODW4S.DAT
01/20/93

ADJUSTER TYPE
Unconfined
SOLUTION METHOD
Bower-Rice

ESTIMATED PARAMETERS
K = 0.01852 ft/min
Y0 = 7.973 ft

TEST DATA
H0 = 4.27 ft
rc = 0.037 ft
rw = 0.33 ft
L = 9.25 ft
b = 9.36 ft
H = 9.36 ft

HODW5S



DATA SET:
a hodw5s.dat
07/21/93

AQUIFER TYPE
Unconfined
SOLUTION METHOD
Bouwer-Rice

ESTIMATED PARAMETERS
K = 0.005631 ft/min
y0 = 1.576 ft

TEST DATA:
HD = 1.75 ft
rc = 0.037 ft
rw = 0.33 ft
L = 9.12 ft
b = 6.53 ft
H = 6.53 ft

K

GROUNDWATER SAMPLING
FIELD PARAMETER RESULTS

**Field Parameters
HOD Landfill
Groundwater Sampling**

	<u>pH</u>	<u>°C</u> <u>Temperature</u>	<u>Specific</u> <u>Conductivity (ohms)⁽¹⁾</u>	<u>Dissolved</u> <u>Oxygen (mg/l)</u>	<u>Oxidation</u> <u>Reduction (mV)</u>
HD-GWUS1S-01	7.38	10.5	760	5.2 @ 9 °C	204 @ 11.3 °C
HD-GWUS1D-01	7.58	11	694	3.6 @ 10.5 °C	69 @ 12.5 °C
HD-GWUS3S-01	7.34	13.5	1025	4.3 @ 12 °C	224 @ 14 °C
HD-GWUS3I-01	8.12	12.5	626	6.9 @ 12 °C	84 @ 13.5 °C
HD-GWUS3D-01	7.34	14	1153	4.7 @ 14 °C	83 @ 10 °C
HD-GWUS4S-01	7.27	9.5	1144	6.2 @ 9 °C	50 @ 10.5 °C
HD-GWUS4D-01	7.82	12.5	546	3.4 @ 12 °C	40 @ 13.5 °C
HD-GWUS6S-01	7.17	11.5	835	3.5 @ 11 °C	63 @ 13 °C
HD-GWUS6I-01	8.17	12.5	680	5.4 @ 12 °C	65 @ 14 °C
HD-GWUS6D-01	7.68	13	598	3.5 @ 11.5 °C	20 @ 14 °C
*HD-GWW3SB-01	7.27	13.5	1298	8.4 @ 13 °C	91 @ 13 °C
*HD-GWW3D-01	7.47	14	1410	NM	98 @ 13.5 °C
*HD-GWW4S-01	6.92	14	1410	9.6 @ 14 °C	147 @ 14 °C
HD-GWW4S-91	6.91	13	1447	9.5 @ 13 °C	138 @ 13 °C
HD-GWW5S-01	6.79	12.5	1133	5.3 @ 12 °C	76 @ 13 °C
HD-GWW6S-01	6.95	12	2229	6.2 @ 11 °C	91 @ 12.5 °C
HD-GWW7D-01	7.88	12.5	600	3.2 @ 12 °C	65 @ 23.5 °C
HD-GWG11S-01	--	--	--	--	--
HD-GWG11D-01	--	--	--	--	--
HD-GWUS6S-91	7.18	10.5	859	4.8 @ 10 °C	57 @ 12 °C
HD-GWFB01-01	6.70	23	41	5.8 @ 23 °C	25 @ 23.5 °C
HD-GWFB02-01	6.65	20.5	10	10.1 @ 20 °C	8 @ 21.5 °C
HD-GWUS4D-91	7.85	12	NM	3.2 @ 11 °C	67 @ 13 °C
HD-FB03-01	7.85	16	26	9.2 @ 16 °C	76 @ 16 °C
HD-LCLP11-01	6.75	13	3947	4.2 @ 11.5 °C	50 @ 14 °C
HD-LCLP1-01	7.16	10	8714	1.6 @ 10 °C	42 @ 11 °C
HD-LCLP1-91	7.19	10	8714	0.8 @ 10 °C	21 @ 11 °C
HD-LCLP6-01	7.17	19	11931	1.0 @ 19 °C	-50 @ 19 °C
HD-LCFB01-01	6.52	13	13	7.0 @ 12.5 °C	40 @ 13.5 °C
HD-LCLP8-01	7.15	25	12900	1.4 @ 26 °C	82 @ 26.5 °C
HD-LCMHE-01	6.78	16	5121	3.4 @ 16 °C	72 @ 16.5 °C
HD-SWS201-01	7.65	17	595	9.0 @ 17 °C	61 @ 17 °C
HD-SWFB01-01	6.54	19	1	7.0 @ 18 °C	35 @ 19 °C
HD-SWS101-01	8.05	22	500	6.0 @ 22 °C	118 @ 22 °C
HD-SWS301-01	7.79	18.5	597	4.6 @ 18 °C	118 @ 19 °C
HD-SWS301-01	7.77	19	539	8.4 @ 19 °C	110 @ 20 °C
HD-VW03-01	7.45 ⁽²⁾	13	658	NM	NM
HD-VW05-01	7.52	15	750	NM	NM
HD-PW01-01	NR	NR	NR	NM	NM
HD-PW02-01	NS	NS	NS	NS	NS
HD-PW03-01	7.91	15	625	NM	NM
HD-PW04-01	7.59	16	609	NM	NM
HD-PW05-01	8.13 ⁽²⁾	15	625	NM	NM

NOTES:

- NM = Parameter not measured
- = Not enough sample in well for field parameters
- * = Wells sampled on June 1, 1993
- mg/l = Milligrams per liter (dissolved oxygen readings)
- mV = Millivolts (oxidation reduction potential)
- (1) = Conductivities corrected to 25°C
- + = Field Parameters not obtained due to lack of enough sample volume
- (2) = pH meter not stabilizing, confidence in reading is low
- NR = Not recorded
- NS = Not sampled

L

METEOROLOGICAL DATA

Meteorological data will
be included in the RI Report.